VILLAGE OF HAMPSHIRE

CALL FOR SPECIAL MEETING

I hereby call a special meeting of the Village Plan Commission to be conducted on Monday, October 15, 2018, commencing at 7:00 p.m., at the Hampshire Village Hall, 234 South State Street, Hampshire, Illinois for the purpose of considering the following item(s):

See attached Agenda for the special meeting, listing three (3) items of New Business.

Dated: October <u>\$\mathcal{\mathcal{L}}\$</u>, 2018

William Robinson

Chairman

Delivered to and received by the Village Clerk this <u>and Solution</u> day of October, 2018.

Linda Vasquez Village Clerk

This Call for Special Meeting should be delivered to the place of residence or abode of the Chair and the members of the Plan Commission (excepting any person making the Call) not less than 48 hours before the date and time of the proposed special meeting.

VILLAGE OF HAMPSHIRE **PLAN COMMISSION**

SPECIAL MEETING **OCTOBER 15, 2018**

AGENDA

CALL TO ORDER:

TIME: 7:00 PM

PLEDGE OF ALLEGIANCE.

ROLL CALL / ESTABLISH QUORUM.

MINUTES: Review and approve minutes of previous meeting.

NEW BUSINESS:

- 1. Consideration and Recommendation regarding Final Plat of Subdivision, together with accompanying Preliminary / Final Plans, for the Hampshire Grove Business Park Subdivision, located at the southeast corner of Higgins Road and Widmayer Road, on land annexed or to be annexed to the Village, pursuant to §7-2-4 of the Village Code.
- 2. Consideration and Recommendation regarding Amended Final Plat of Subdivision for Old Mill Manor Subdivision, Unit 10 and Old Mill Manor Subdivision, Unit 11, located on Oak Knoll Drive / IL 72 in the Village.
- 3. Consideration and Recommendation regarding Concept Plan for Tri County Self Storage site and subdivision, for property located on US Highway 20 west of the Hampshire Corporate Center Subdivision (to be annexed to the Village).

OLD BUSINESS: None.

PUBLIC COMMENT: All persons wishing to make public comment must sign in prior to the start of the meeting. Time shall be limited to a maximum of five (5) minutes for each speaker and not more than thirty (30) minutes total.

NEXT MEETING DATE: TBD

ADJOURNMENT.



September 28, 2018

Village of Hampshire Plan Commission 234 S. State Street Hampshire, IL 60140

Re:

Preliminary Plan and Final Plan Submittal

PetAg Project / Hampshire Grove Business Park

Hampshire, Illinois

Dear Plar Commission Members:

Norther Builders, Inc. formally requests the Plan Commission review and consideration for the approval of both the Preliminary Plan and Final Plan Submittal for the PetAg projectlocated on 15.98 acres in the proposed Hampshire Grove Business Park located immedately west of the Hampshire Woods Business Park.

This-ubmittal request follows the Plan Commission's previous approval of Concept Plangranted on September 10th.

The btAg property is part of an 80 acre parcel that is currently in the process of gaining the Vage's approval for both zoning and annexation; that process is well under way and he received the support of the Zoning Board as well as the Village Board.

We has included the required information; please see our attached narrative and exhibit. We ask for your review, consideration and respectfully request your approval and yolpositive recommendation that it be presented to the Village Board for their approval

Thank yagain for your consideration

Very trulyurs.

Brian M. No, Vice President

Cc: Matthewisecki, Sr. Vice President

NORTHERN BUILDEIC.

5060 River Road Schiller Park • Illinois • 1076 847/678-5060 • FAX: 8-7670 www.northernbuilders.c

ROBERT ARTHUR LAND COMPANY, LLC

PO BOX 610

BATAVIA, IL 60510

630-879-8703 (O)

630-207-8793 (M)

August 7, 2018

Village of Hampshire Hampshire Village Hall 234 South State Street Hampshire, IL 60140

Re: Permission to Submit Land Development Application

To Whom it May Concern,

Robert Arthur Land Company, LLC owns RALC Hampshire, LLC who owns 403 acres bounded by Higgins Road to the north, Big Timber Road to the south, Harmony Road to the east and the Hampshire Woods Business Park to the east.

Northern Builders, Inc. is the contract purchaser of 14.7 acres of the 80 acre parcel east of Widmayer Road and they have our permission to process the Land Development Application for the annexation, zoning and subdivision of the 14.7 acres.

Sincerely,

Arthur C. Zwemke Manager

Rahgpslda1





PETAG PROJECT, HAMPSHIRE ILLINOIS LIST OF ADJACENT PROPERTY OWNERS

Zip Code	60510 60510 60140-8245 60140 60068-5338 60178 60510	Zip Code 60010-6967 60010-6967 60010-6967 60140 60706 60706
State	Illinois Illinois Illinois Illinois Illinois Illinois	State Illinois Illinois Illinois Illinois Illinois Illinois
Town	Batavia Batavia Hampshire Hampshire Park Ridge Sycamore Batavia	Town North Barrington North Barrington North Barrington Hampshire Harwood Heights Harwood Heights
Street Address	PO Box 610 PO Box 610 200 Flannigan Rd 234 S State St 503 W Talcot Rd 1845 Elizabeth Cir PO Box 610	Street Address 104 S Wynsote Park Dr 234 S State St 7239 W Wilson Ave 7239 W Wilson Ave
Name (from tax records)	RALC Hampshire LLC RALC Hampshire LLC Sysco Asian Foods Inc. Buckhead Illinois Village of Hampshire c/o Michael Biasiello Bean, George E & Joyce RALC Hampshire LLC	Name (from tax records) c/oWade B Light c/o Wade B Light c/o Wade B Light Village of Hampshire Wayne Hummer Trust Company Wayne Hummer Trust Company
Property Owners immediately adjacent to the PetAg property Noted as Index Number Property Owner	1 01-11-100-005 RALC Hampshire LLC 2 01-11-100-006 RALC Hampshire LLC 3 01-11-127-003 Sysco Asian Foods, Inc 4 01-11-127-004 Village of Hampshire 5 01-11-300-001 Trust #8002358312 6 01-10-400-017 7 01-10-200-001 RALC Hampshire LLC	Property Owners immediately adjacent to the 80 acre parcel Index Number Property Owner 8 01-02-300-011 Harris Trust & Savings Bank, Trustee TR # HTB-1464 9 01-02-300-011 Harris Trust & Savings Bank, Trustee TR # HTB-1464 10 01-02-300-012 Harris Trust & Savings Bank, Trustee TR # HTB-1464 11 01-11-100-090 Village of Hampshire 12 01-11-100-014 Hummer, Wayne Tr. Co. Trustee Tr. #Lft 1745 13 01-11-127-001 Hummer, Wayne Tr. Co. Trustee Tr. #Lft 1745 14 01-11-127-002 Hummer, Wayne Tr. Co. Trustee Tr. #Lft 1745
Property Owne Not		Property Owne

Morthern Builders, Inc.

PETAG PROJECT, HAMPSHIRE ILLINOIS MAP OF ADJACENT PROPERTY OWNERS





HAMPSHIRE GROVE BUSINESS PARK

BEING A SUBDIVISION OF PART OF THE WEST HALF OF THE NORTHWEST QUARTER OF SECTION 11, IN TOWNSHIP 42 NORTH, RANGE 6 EAST OF THE THIRD PRINCIPAL MERIDIAN, IN THE TOWNSHIP OF HAMPSHIRE, KANE COUNTY, ILLINOIS

PROPERTY DESCRIBED IN THE FORECOMA SUPECIORS CHERT EXAME AND HAS CASSED HE PROPERTY DESCRIBED IN THE FORECOMA SUPECIORS CHERT IF CALL AND HAS CASSED HE WAS CASSED THE CASSED HE WAS CASSED THE CASSES HERE IN SET TORTH AS A LIVEUED AND PROPUBLE FOR BY STATULE AND DIES HEREBY ACKNOWLEDGE AND AUDIT THE SAME UNDER THE STYLE AND TITLE THEREON MODICARY.

THE UNDERSORD MERIEN EUROLAIES FOR PUBLIC USE THE LANDS SHOWN ON HITS PLAT OR HORDCOMPARES, THEREIS, ALLEY AND PUBLIC SERVICES, AND HEBELY ALSO RESERVES FOR MAY ELECTRIC, CAS, ELECTRICE, CABLE TV OR OTHER TELECOMAUNICATIONS COMPANY UNDER FRANCHISE AUGUELANT WITH "VILLACIO" OF MANESHEET, THEIR SUCCESSORS AND ASSIGNS, THE EXSEMENT PROVISIONS WHICH ARE STATED HEREON.

UNDERSIGNED FURTHER CERTIFIES THAT ALL OF THE LAND INCLUDED IN THIS PLAT LIES IN THE BOUNDARIES OF COMMUNITY UNIT SCHOOL DISTRICT 300

The ALLES CREATIONS OF THE CONTROL OF THE CONTROL OF THE CALLED OF THE C

BANK NAME

BESCHIEBE HEREIN, HEREIY CONSENTS TO THE EXECUTION AND RECORDING OF THE ABOVE AND TOGEODING THAT OF SUBDIVISION AND HEREBY SUBMITS ITS MUNICAGE RECORDED

AS DOCUMENT NUMBER

BEFORE ME THIS DAY AND ACKNOMEDEED THAT AS SUCH DEFICERS. THET SUCKE AND DELIVERED THE SALD INSTRUMENT AND CAUSED THE CORPORATIC SEA OF DE REFUSED THERE DAY THE REFER AND VOLUNTARY ACT AND AS THE FREE AND VOLUNTARY ACT OF SAID CORPORATION, FOR THE USES AND PURPOSES THERE ME SET TONTY.

AT AND SERVICE AND AND THE COUNTY AND STRONALLY KNOWN TO ME TO BE OFFICERS OF CORPORATION AS SHOWN ABOVE, APPERING THE COUNTY AND ASSESSMENT ASSESSMENT AND ASSESSMENT ASSESSMENT ASSESSMENT ASSESSMENT ASSESSMENT AND ASSESSMENT ASSESSM

AFORESAID, DO HEREBY

IN THE OFFICE OF THE RECUMBER OF DEEDS TO ALL OF THE PROVISIONS THEREOF, IN WITNESS WHEREOF, THE SAID

SANK
STRUMENT TO BE SIGNED BY ITS DULY AUTHORIZED
OWN STATE , THIS ___DA

NK HAS CAUSED
RIZED OFFICERS ON 11'S BEHALF
DAY OF , 20 ...

PREPARED FOR: NORTHERN BUILDERS, INC. 5060 RIVER ROAD SCHILLER PARK, ILLINOIS 60176

DWMME RALC HAMPSHIRE, LLC C/O
C/O
C/O
RATHUR C. ZWEMKE, MANAGER
ROBERT ARTHUR LAND COMPANY
P.O. BOX 610
BATAVIA, ILLINOIS, 60510


FOR REVIEW PURPOSES ONLY

THIS INSTRUMENT ... WAS FILED FOR RECORD IN INE RECORD OFFICE OF KAME COUNTY, ILLINOIS, ON THE DAY OF DAY OF AT UCLOCK ... M. AND MAS RECORDED IN PLAT ENVELOYE NO.

-ROFESSIONAL LAND SURVEYOR STATE OF ILLINOIS STATES CETTED THAT COLL SUBDIVISION MANUMENTS WITL BE SET, AND THATE DESCRIPTION OF THE WORLD STATES OF THE WORLD STATES OF THE COLL STATES OF THE COLUMN THE

LRRY P. CHRISTOPH, 1.P.L.S. NO ICENSE EXPIRES: 11-30-2018 VALIO DNLY IF EMBOSSED SEAL AF ILLINOIS) SS

SUBDIVIDER:
NORTHERN BUILDERS, INC.
5060 RIVER ROAD
SCHILLER PARK, ILLINOIS 60176










847.303.1155





SITE AREA (±80.00 AC.)

±3,484,800 S.F.

CONCEPTUAL PLAN FOR:

HAMPSHIRE GROVE

BUSINESS PARK

HAMPSHIRE, ILLINOIS



SITE PLAN

Q

HARRIS ARCHITECTS, INC.
HITECTS.COM 847.303.1155

ROADWAY IMPROVEMENT PLANS

RYAN DRIVE EXTENSION AT HAMPSHIRE GROVE BUSINESS CENTER

HAMPSHIRE, ILLINOIS PROJECT NO:10366

DEVELOPER

INTERIOR STATE OF THE PROPERTY OF THE PROPERTY

NORTHERN BUILDERS, INC. 5060 RIVER ROAD SCHILLER PARK, IL 60176 PH: 847-678-5060

CALL J.U.L.I.E. 1-800-892-0123

WITH THE FOLLOWING: COUNTY KANE

CITY, TOWNSHIP HAMPSHIRE, T42N SEC. & 1/4 SEC. NO. SEC 11 NW 1/4


> 48 HOURS BEFORE YOU DIG. EXCLUDING SAT., SUN. & HOLIDAYS

INDEX					
SHEET #	SHEET I.D.	SHEET DESCRIPTION			
1	C1	COVER SHEET			
2	GN	TYPICAL SECTIONS & GENERAL NOTES			
3	ΕT	EXISTING CONDITIONS PLAN			
4	GM1	GEOMETRIC LAYOUT PLAN			
5	PP1	PLAN AND PROFILE			
6	GR1	GRADING PLAN			
7-8	SP1-SP2	SPECIFICATIONS			
9-11	SE1-SE3	SOIL EROSION AND SEDIMENT CONTROL PLANS			
12-14	D1-D3	DETAILS			

BENCHMARK

DESCRIPTION: SEE SHEET GN FOR BENCHMARK INFORMATION NOTE:

SPACECO, INC. AND THE VILLAGE ARE TO BE NOTIFIED AT LEAST THREE (3) DAYS PRIOR TO STARTING CONSTRUCTION AND SHALL BE INCLUDED IN THE PRECONSTRUCTION MEETINGS



DRAINAGE CERTIFICATION

REGISTERED PROFESSIONAL ENGINEER

	REVISIONS					
Ol	ORIGINAL PLAN DATE: SEPTEMBER 26, 2018					
#	SHEET	#	REMARKS	DATE		
1						
T						
T						
+						
1			10.000			
1						
+						
†						
$^{+}$	1970					
+						
+				-		
+						
+		_				

ENGINEER MICHAEL MONDUS, P.E. ILLINOIS REGISTRATION NO.: 062-052057 EXPIRATION DATE: 11/30/2019 THESE PLANS OR ANY PART THEREOF SHALL BE CONSIDERED VOID WITHOUTHE SIGNATURE, SEAL, AND EXPIRATION DATE OF SEAL OF THE ENGINEER

ISSUED FOR REVIEW 09/26/18

10is 60018 696-4065

9575 W. Higgins Road, Suite 700, Rosemont, Illin Phone: (847) 696-4060 Fax: (847)

10366TITLE

09/26/18

10366

C1

GENERAL NOTES AND CONSTRUCTION SPECIFICATIONS

- The "Standard Specifications for Road and Bridge Construction" adopted APRIL 1, 2016, the
 "Standard Specifications for Water and Sewer Main Construction in Illinois", 5tht Edition, dated
 ANURSH: 2014 and revisions therebo, these improvement plans and details, special provisions and
 codes and ordinances of the Village of Hampshire, Illinois shall govern applicable portions of this
 project.
- The Contractor shall obtain, erect, maintain and remove all signs, barricades, flagmen and other control devices as may be necessary for the purpose of regulating, warning or guiding traffic. Placement and maintenance of all traffic control devices shall be in accordance with the applicable parts of Article 107.14 of the Standard Specifications, the "Standard Specifications for
- Locations of utilities shown on plans are approximate only, and are not necessarily complete. Contractor shall make his own investigations as to location of all existing underground structures cables, utilities and pipe lines.
- If existing utility lines of any nature are encountered which conflict in location with new construction, the Contractor shall notify the Engineer and Village so that the conflict may be resolved.
- The Contractor shall notify J.U.L.I.E. (1-800-892-0123) at least ten days prior to construction so that each utility company can stake out any underground improvements that they may have which might interfere with the proposed construction.
- The Contractor shall be required to make arrangements for the proper bracing, shoring and other required protection of all roadways, structures, poles, cables and pipe lines, before construction begins. He shall be responsible for any damage to the streets or roadways and associated structures and shall make repairs as necessary to the satisfaction of the Engineer and Village at
- The Contractor shall be responsible for the protection of all private and public utilities even though they may not be shown on the plans. Any utility that is damaged during construction shall be repaired or pelpaced to the satisfaction of the Engineer and Village by the Contractor at his own
- The Contractor shall examine the plans and specifications, visit the site of the work and inform himself/herself fully with the work involved, general and local conditions, all Federal, State and local laws, ordinances, rules and regulations and all other pertinent items which may affect the cost and time of completion of this project before submitting a proposal.
- All work and materials shall be in accordance with code requirements
- Prior to submitting his bid, the Contractor shall call the attention of the Engineer to any material or equipment he deems inadequate and to any item of work omitted
- The pay items shall be as noted in the Summary of Quantities/Proposal. Any item of work that is shown on the plans to be performed by the Contractor, for which there is no pay item, shall be considered incidental to the cost of the project.
- Structures for valve vaults for water mains shall be in accordance with the improvement plans and the applicable standard specifications. Where granular trench backfill is required around these structures, the cost shall be considered as incidental and shall be included in the contract unit crice for the structure.
- Frame and cover or grates for water main structures shall be as indicated within these
- All final adjustments of casting will be accomplished by the use of precast concrete adjusting rings set in Butyl rope joint sealant; mortar joints will not be allowed. Total height of adjusting rings used shall not exceed eight (8") inches. Cost for adjustment is considered incidental.
- The underground contractor shall be responsible to place on grade and coordinate with other contractors all underground structure frames such as catch basins, inlets, manholes, hydrants, buffalo boxes, valves, etc. No additional compensation shall be paid and said adjustments shall be considered incidental to other items of construction.
- The Contractor shall restore any area disturbed to a condition equal to or better than its original use. This shall include finish grading, establishment of a vegetative cover (seeding or sod), general cleanup and pavement replacement.
- All trenches caused by the construction of sewers, water mains, water service pipes and the All trenches caused by the construction of sewers, water mains, water service pipes and the excavation around catch basins, manholes, intelles and other appurtenances which occur within the limits of existing or proposed pavements, sidewalks and curb and gutters or where the edge of the trench shall be within two (2) freet of said improvements shall be backfilled with compacted granular trench backfill or with approved suitable select material and properly compacted in accordance with Division II Section 20 of the "Standard Specifications for Water and Sewer Main Construction in Illinois", Sixth Edition, Dated July, 2009, and revisions thereto.

Trench backfill quantities for public utilities and utility conduits have been computed and shall be paid for based on the following maximum trench widths in accordance with Division II of the "Standard Specifications for Water and Sewer Man Construction in Illinois", Skith Edition, Dated July, 2009, and revisions thereto. The depth of backfill shall be measured from the top of pipe embedment to the finished subgrade or as noted on the plans.

Trench Depth/ Protection

Required Trench Width on Each Side of the Pipe

12 in. (300 mm) 18 in. (450 mm) 18 in. (450 mm) 5 ft (1.5 m) and less, without protection 5 ft (1.5 m) and less, with protection Greater than 5 ft (1.5 m)

Trench backfill required in excess of the quantity beyond the maximum trench width shall be considered incidental to the contract unless authorized by the Engineer.

- The Contractor shall be responsible for providing safe and healthful working conditions throughout
- The Engineer will be given forty-eight (48) hours notice for any staking that is to be done. Each of the various items of work covered by this contract will be staked once. Additional staking required due to the negligence of the Contractor shall be paid for by the Contractor at the current hourly rate.

- The Contractor shall inform the Village Engineer before work commences on each category of construction, i.e. water main, grading, pavement and drainage improvement. A twenty-four (24) hour notice shall be given for any item that requires final testing and inspection such as water mains or sanitary sewers.
- The Engineer will furnish the Contractor with lines and grades necessary to the proper prosecution and control of the work. The Contractor shall call the attention of the Engineer to any errors or discrepancies which may be suspected in lines and grades which are established by the Engineer; and shall not proceed with the work until any lines and grades which are believed to be in error have been verified or corrected by the Engineer or his representative.
- All lot irons damaged or removed during construction of this project shall be replaced by the Engineer and said cost of replacement shall be paid by the Contractor
- Before acceptance by the Village and final payment, all work shall be inspected and approved by the Village Engineer. Final payment shall be made after all of the Contractor's work has been approved and accepted.
- The Contractor will have in his possession on the job site a copy of the plans and specifications
- If any approved equal items are required, the Contractor shall contact the Engineer for approval.
- Any drain and/or field tile encountered by the Contractor during the installation of the improvements shall be returned to original condition. This work to be considered incidental to the control of th
- All road signs, street signs and traffic signs which need to be relocated or moved due to construction shall be taken down and stored by the Contractor at his own expense, except those which are necessary for proper traffic control which shall be temporarily reset until completion of construction operations. After completion of the work, the Contractor shall reset, at his expense,
- The Contractor shall dispose of all excess excavation, unsuitable and unusable materials offsite and at an approved location in a manner that public or private property will not be damaged or endangered. This work is considered as incidental to the cost of the project.
- "Band-Seal" or similar couplings shall be used when joining sewer pipes of dissimilar materials
- As-built drawings shall be prepared by the Contractor and submitted to the Engineer as soon as the site improvements are completed. Any change in length, location or alignment shall be shown
- The Contractor is responsible for coordinating any required inspections with the Village of
- Special attention is drawn to the fact that Article 105.06 of the standard specifications requires the Contractor to have a competent superintendent on the project site at all times, irrespective of the amount of work sublet. The superintendent shall be capable of reading and understanding the plans and specifications, shall have full authority to execute orders to expectite the project, shall be responsible for scheduling and have control of all work as the agent of the Contractor. Failure to comply with this provision will result in a suspension of work as provided in Article 108.07.
- The Engineer and Village are not responsible for the construction means, methods, techniques, sequences or procedures, time of performance, programs or for any safety precautions used by the Contractor. The Contractor is solely responsible for execution of his work in accordance with the contract documents and specifications.

	LEGEND	
EXISTING	DESCRIPTION	PROPOSED
· ·	DRAIN TILE	
->>-	STORM SEWER	->>
->>-	SANITARY SEWER	->>
>>->>-	SANITARY TRUNK SEWER	→
w	WATER MAIN (WITH SIZE)	-w
	PIPE TRENCH BACKFILL	20.70.1.0.000
-cc-	GAS MAIN	
-тт-	TELEPHONE LINES	
-ε	ELECTRIC LINE	-EE-
×	FENCE	—х
	RIGHT-OF-WAY	
	EASEMENT	
	PROPERTY LINE	
	SETBACK LINE	
	CENTERLINE	
680	CONTOUR	680
0	SANITARY MANHOLE	0
0	STORM MANHOLE	0
0	CATCH BASIN	•
	INLET	-
α	FIRE HYDRANT	4
	PRESSURE CONNECTION	€
	PIPE REDUCER	>
⊖ ⊛	VALVE AND VAULT, VALVE	9
٥	FLARED END SECTION	4
¤	STREET LIGHT	×
•	UTILITY POLE	•
Δ	CONTROL POINT	
d	SIGN	4
XXXXX	SPOT ELEVATION	xxx-xx
•	SOIL BORING	•
	OVERLAND FLOW ROUTE	-
	DRAINAGE SLOPE	→ OR →
0 0	GUARDRAIL	
~ ~	WATER'S EDGE	~
	CONCRETE	[::::]
	REVERSE PITCH CURB	mmmmmmm
~~~	TREE, FIR TREE, BUSH, &	**
·)(.)()	PROPOSED TREE TO REMOVE	$\otimes$

## ABBREVIATIONS

TF . TOP OF FOUNDATION

M - STORM MANHOLE I - INVERT OR INLET

S - SANITARY MANHOLE

CB - CATCH BASIN LP - LIGHT POLE

E - END SECTION

FH - FIRE HYDRANT GR - GRADE RING (HYDRANT

DESCRIPTION

IHPA

IDNR

IEPA NOI

IEPA PUBLIC WATER SUPPLY IEPA POLLUTION CONTROL

GF - GARAGE FLOOR

TW - TOP OF RETAINING WALL

TC - TOP OF CURB TD - TOP OF DEPRESSED CURB

BW - BOTTOM OF RETAINING WALL OP - OUTLET OF PIPE

PERMITS

LOG NO.

004081618

T/P . TOP OF PIPE B/P - BOTTOM OF PIPE WM - WATERMAIN SAN - SANITARY SEWER

STM - STORM SEWER LO - LOOK OUT

PLO - PARTIAL LOOK OUT

AN DRIVE EXTENSION / HAMPSHIRE, ILLINOIS RYAN I TYPICAL PERMIT NO. DATE ISSUED 09/21/2018 08/13/2018

NOTES

GENERAL

AT

## CONTACT INFORMATION

1901524

## VILLAGE ENGINEER

ENGINEERING ENTERPRISES, INC 52 WHEELER ROAD SUGAR GROVE, IL 60554 PH+ 630-465-4700 CONTACT: BRAD SANDERSON

## BENCH MARK

SOURCE BENCHMARK; NATIONAL GEODETIC SURVEY PID. DL6745
STATION IS STAINLESS STEEL ROD IN SLEEVE LOCATED
ABOUT 4.5 ML (7.2 KM) EAST OF HAMPSHIRE.
4.1 (6.6 KM) ML SOUTH-SOUTHWEST OF HUNTLEY AND
3.3 ML (5.3 KM) NORTH-HORTHWEST OF PINGREE GROVE.
ELEVATION = 909.57 NAVD 88 SOURCE BENCHMARK: NATIONAL GEODETIC SURVEY


KI31
PID: NHO213
STATION IS BENCH MARK DISK SET IN TOP OF CONCRETE MONUMENT LOCATED 0.9 MI SOUTHEAST FROM HAMPSHIRE. ELEVATION = 919.43 NAVO 88




10366GN.DGN DATE:


10366


GN 2 OF




TYPICAL ROAD SECTION N.T.S.









EADTHWON'S MATER	PAVING NOTES
	1. GENERAL
EARTHWORK NOTES  1. GENERAL  A. IT IS THE CONTRACTOR'S RESPONSIBILITY TO UNDERSTAND THE SOIL AND GROUNDWATER CONDITIONS AT THE SITE. THE CONTRACTOR SHALL DETAIN AND READ THE GEOTECHNICAL REPORTS ANALUSEE FROM THE OWNER.  8. ANY QUANTITIES IN THE BID PROPOSAL ARE INITIADED AS A QUIDE FOR THE CONTRACTOR'S USE IN OFTERNAINING THE SOOPE OF THE CONTRACTOR PROMEET. IT IS THE CONTRACTOR'S SHE SPONSIBILITY TO CHEMINA ALL MATERIAL OUANTITIES AND APPRAISE HINGLIE OF ALL SITE CONDITION. THE CONTRACT PRICE SIMBLITED WITH ALL MATERIAL OUANTITIES AND APPRAISE HINGLIE OF ALL SITE CONDITION. THE CONTRACT PRICE SIMBLITED WITH ALL MATERIAL OUANTITIES AND APPRAISE HINGLIE OF ALL SITE CONDITION. THE CONTRACT PRICE SIMBLITED WITH ALL MATERIAL OUANT THE SHALL MAINTAIN POSITIVE DRAINAGE DURING CONSTRUCTION FLANS ARE FINISHED GRADE ELEVATIONS AND THAT PAPERAIT THICKNESS. TOSPOIL E.CT. MAYS BE SUBMANCED TO DETERMINE SIMBLADE CHAPTER ANY RINNING. MIDD CAMPENSATION REQUESTED DUE TO DELAYS OR INSULTABLE MATERIALS CREATED AS A RESULT THEREOF. FINAL GRADES SHALL BE PROTECTED AGAINST BANKE FROM DESCRIPTION BORNING THAT THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE DURING CONSTRUCTION. AND APPROVED SHALL REGISTED ANY THE REPORT OF THE SITE DEVIATED IN ADDITIONAL CONFESSION OF THE STRENGT FROM RESPONSIBLE FOR THE APPROVED.  5. PLANS FOR THE SITE DEVIATED IN A DOILT ON A DOILT ON A DOILT ON A DOILT ON THE FOR THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLICATION OF THE "SOIL GROCE ON ANY THE FORE THAT THE ADDITIONAL CONFESSION OF THE APPROVED FROM THE TOTAL CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLICATION OF THE "SOIL GROCE ON ANY THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLICATION CONTRACTOR SHALL BE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLICATION CONTRACTOR SHALL CONTRACTOR SHALL BE SERVED AND THE TOTAL CONTRACTOR SHALL BE SERVED AND THE TOTAL CONTRACTOR SHALL BE SERVED AND THE TOTAL CONTRACTOR.  5. PRICE TO COMMENCEWAY TO FORD AND THE TOTAL SHALL BE SERVED AND THE TOTAL SHALL BE SERVED AND THE TOTAL SHALL BE SHALL BUTHALL SHALL BE SHALL BUTHA	1. CENERAL  A. PAYING WORK INCLUDES FINAL SUBGRADE SHAPING, PREPARATION AND CORPECTION: PLACEMENT OF SUB-BASE DR BASE COUNTY WITH 18.5. BITMANDUS BINGER AND/OR SUBFACE COURSES; FORWING, FINISHING AND CUPING CONCRETE PAYEMENT, CURBS AND MALES. AND THAN CLEAN-UP AND ALL RELATED WORK.  8. COMPACTION REQUIREMENTS, INSCREAMS COURSES, WHETER TO SSBER ARTICLE GAG. OT. ACCIDENTS BEST STEED FOR SUBJECT OF SUBJECT
MATERIAL BETWEN THE TOPSOIL AND CLAY. THE TRANSITIONAL MATERIAL SHALL BE USED IN NON-SHOULDHART FILL  DETOPSOIL RESPREAD SHALL INCLUDE HALLING AND SPRADING 6" OF TOPSOIL OVER AREAS TO BE LANDSCAPED WHERE SHORN ON THE PLANS OF DIRECTION BY THE OWNER.  E. MODERATE COMPACTION IS REQUISED IN MON-STRUCTURAL FILL AREAS.  3. EARTH EXCAVATION INCLUDES:  A. EXCAVATION INCLUDES:  A. EXCAVATION INCLUDES:  A. EXCAVATION INCLUDES:  A. EXCAVATION OF CLAY AND DIRER MATERIALS WHICH ARE SUITABLE FOR USE AS STRUCTURAL FILL. THE EXCAVATION SHALL BE TO WITHIN A TOLERANCE OF 0.1 FEET OF THE PLAN SUBGRADE ELEVATIONS WHILE MAINTAINING PROPER DRIANGE. THE TOLERANCE WITHIN PAYER AT MEAS SHALL BE SUBHING ELEVATIONS WHILE MAINTAINING PROPER DRIANGE. THE TOLERANCE WITHIN PAYER AT MEAS SHALL BE WITHIN INDEX AREAS ROUGHING STRUCTURAL FILL IN DUBBE TO MATERIAL BE RADIUSTED AS SHALL BE WITHIN INDEX AREAS ROUGHING STRUCTURAL FILL IN DUBBE TO MATERIAL BE ADJUSTED IN DODER TO CAPITED FROM THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MATERIAL SHALL BE STRUCTURAL FILL MATERIAL MAY BE THE ACCOUNTED THE MAY BE AND SHOULD BE STRUCTURAL FILL. FILL MATERIAL SHALL BE AND SHALL WITH BE MADER AS STRUCTURAL FILL SHALL BE AT LEAST 93T OF THE MATERIAL SHALL BE AND SHALL WITH BE AMERICAN TO THE HEADY HAND SHALL BE AT LEAST 95T OF THE MODIFIED PROCESSITY WITH PROPOSED BUYCHEN MATERIAL BE MATERIALS UNLESS.  SPECIFICALLY DIRECTED BY A SOILS EXCURRENT OF THE CONCURRENCE OF THE MADERIAL SHALL BE AT LEAST 95T OF THE MODIFIED PROCESSITY WITH PROPOSED BUYCHEN MAY BE MATERIAL BUYCHEN TO BE AND SHALL BE AT LEAST 95T OF THE MODIFIED PROCESSITY	B. COMERTE LUBS AND MORP COMBINATION CURB AND GUITER SHALL BE OF HE TIPE SHOWN ON THE PLANS. THE CONTRACTOR IS CAUTIONED TO REFER TO THE CONSTRUCTION STANDARDS, AND THE PRIVATENT CROSS-SECTION OF THE PLANS AND THE PRIVATENT CROSS-SECTION OF THE PLANS AND THE PRIVATENT CROSS-SECTION OF THE PLANS AND THE PRIVATE CROSS OF THE COMERT CROSS-SECTION OF THE PLANS AND THE PLANS AND THE PRIVATE CROSS OF THE DOMES AND SHALL BE PROVIDED AS MORE CONTRACTOR OF THE DOMES AND THE CHARGE AND THE CHARGE AND THE CONTRACTOR OF THE COMERT CROSS OF THE CROSS OF
4. UNSUITABLE MATERIAL.  UNSUITABLE MATERIAL SHALL BE CONSIDERED AS MATERIAL WHICH IS NOT SUITABLE FOR THE SUPPORT OF PAVENENT AND BUILDING CONSTRUCTION. AND IS ENCOUNTERED BELEOW NORMAL TOPOSIL DEPINS AND THE PROPERSE SUBCRADE ELEVATION. HE DECISION TO RELIEVE SAID MATERIAL. AND TO WHAT EXTENT, SHALL BE MADE BY A SOILS ENGINEER WITH THE CONCERNEC OF THE UNDERSCOON DIFFERENCE SHALL.  A. SPREAD AND COMPACT UNITORN TO THE DECOREE SPECIFIED ALL EXCESS TRENCH SPOIL AFTER COMPLETION OF THE UNDERSCOON DIFFERENCE, AND COMPACT, TO THE UNDERSCOON DIFFERENCE AND COMPACT, AND THE UNDERSCOON DIFFERENCE AND COMPACT, TO THE UNDERSCOON DIFFERENCE AND COMPACT, AND THE WAS DESCRIBED. THE UNDERSCOON DIFFERENCE AND COMPACT, AND THE WAS DESCRIBED. THE UNDERSCOON DIFFERENCE AND COMPACT, AND THE PROPERS OF ACHIEVEN OF THE PURPOSE OF ACHIEVEN OF THE SECRET COMPACT ON.  C. PROVIDE MATER TO JOB TO DRY MATERIAL IN DOBER TO ADJUST THE MOISTURE CONTENT FOR THE PURPOSE OF ACHIEVEN. THE SECRET COMPACT ON.  BACKFILL HE CURBA SHALL NOT USE BACKFILLED WITHIT THE CONCERNET HAS DURED FOR AT LEAST TO BATS.  TERSCHE COMPACTION: AN TERSCHES SHALL BE COMPACTED BY WEARHING ALL COMPACT ON ANY OF THE BASE CORRECT ON THE SOILS ENGINEER WITH PROPER COMPACT ON ANY OF THE PURPOSE OF ADDITIONATE OF THE SUPPLIES OF THE SOILS ENGINEER WITH PROPER COMPACT ON ANY OF THE PURPOSE OF ADMICTION AND REPURPOSE OF ADMICTION OF THE SOILS ENGINEER WITH PROPER COMPACT ON ANY OF THE PURPOSE OF THE SOILS ENGINEER WITH PROPER COMPACT ON ANY OF THE SOILS ENGINEER AND THE MATERIAL THE OTHER THAN OF THE SOILS ENGINEER OF THE SOILS ENGINEER OF THE SOILS ENGINEER AND THE MATERIAL THE CONTROL OF THE MATERIAL THE PURPOSE OF THE SOILS ENGINEER AND THE MATERIAL AND THE SOILS ENGINEER AND THE MATERIAL AND THE SOILS ENGINEER OF THE SOILS ENGINEER AND THE SOIL	4. FLEXIBLE PAVEMENT  A. HIP PAVEMENT MAIRRIALS FOR BITUMINOUS STREETS. PARKING LOTS, DRIVEWAYS, SIDEMALES AND PATHS  SHALL BE AS DIFFALED ON THE PLANS. UNLESS OTHERWISE SHOWN ON THE PLANS. THE FLEXIBLE PAVEMENTS SHALL  CONSIST OF ACCREGATE BASE COURSE. TYPE BY BITUMINOUS CONCRETE BINDER COURSE! DAYS THE FLEXIBLE PAVEMENTS SHALL  CONSISTOR OF ACCREGATE BASE COURSE. THE BY BITUMINOUS CONCRETE BINDER COURSE! DAYS  CONSISTOR TO BE THE MINIMUM COMPARITO THE LOUNG. THE COURSE SHALL BE SUBMITTED THE BY
SIGNING AND PAVEMENT MARKING	TREE PROTECTION
1. ALL SIGNING AND PAYMENT MARRING SHALL BE IN ACCORDANCE WITH THE ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES INJECTS, THE STANDARD SPECIFICATIONS FOR APADD AND BRIDGE CONSTRUCTION ISSUEDS. MUNICIPAL CODE AND THESE PLANS.  1. CONTRACTOR SHALL STANDISH LOCATION OF ALL SIGNS AND MARRINGS FOR APPROVAL BY THE DWHER PRIDR ID INSTALLATION.  3. SIDNS STORY SHALL BE CONSTRUCTED OF O.OND INSH THICK, FLAT ALLWHOUN PANKS WITH REFLECTORIZED LECTING OUT THE FACE IN ACCORDANCE WITH ISSUED SECTION 720. LECEND SHALL BE IN ACCORDANCE WITH MUTTO AND AS SHOWN ON THE PLANS.  4. PODSTS: SIGN POSTS SHALL BE A HEAVY DUTY SITEL, "U" SHAPPO CHANNEL, WE TORING 3.0 POUNDS/FOOT SUCH AS A TYPE B METAL POST SHE SESSED SECTION 729 (DR. 2° PEREPORTACE) SITEL THERE RESIDES SECTION 728].  5. SIDNS AND POSTS SHALL BE INSTALLED IN ACCORDANCE WITH THE ABOVE ISSUED SECTION SHOULD SECTION 728].  6. PAYMENT MARRINGS: ALL PAYMENT HE MAS INSTALLED IN ACCORDANCE WITH THE ABOVE ISSUED SECTION SHOULD SECTION THE PLANS.  6. PAYMENT HARRINGS: ALL PAYMENT HE MAS IN SIDNING THE PROBABILIST OF THE SHOPS SHOULD SECTION THE CONTROL OF THE PAYMENT. CHECK WITH ARROYS THE PROBABILIST.  6. PAYMENT HARRINGS: ALL PAYMENT HOW THE PLANS. INDIFFICE SECTION THE SHOPS.  6. PAYMENT HARRINGS: ALL PAYMENT HOW THE PLANS HAVE BEEN OF THE PAYMENT. CHECK WITH ARROYS TO PROBABLE SECTION THE SHOPS.  6. PAYMENT HARRINGS: ALL PAYMENT HOW WILL MAKEN THE PROBABILIST ON THE PLANS. SECTION THE PAYMENT. CHECK WITH ARROYS THE WILL MAKEN THE PAYMENT.  6. PAYMENT HARRINGS ON RIFE PAYMENT. CHEM WILL MAKEN THE PAYMENT HAS CORDANCE WITH MICH SHOP SHOPS AND THE PLANS. SECTION THE PAYMENT.  6. PAYMENT HARRINGS ON RIFE PAYMENT. PAYMENT CHEM HAVE BEEN AND SHOP THE PLANS. SECTION THE PAYMENT.  6. PAYMENT HARRINGS ON RIFE PAYMENT. CHEM WITH HE PAYMENT HAS CORDANCE WITH MICH TO SHOP THE PAYMENT.  6. PAYMENT HAS READED TO AND THE PAYMENT HARRINGS SHALL HE IN ACCORDANCE WITH MICH THE PAYMENT.	1. EXISTING PARKWAY TREES LOCATED WITHIN THE RICHT OF WAY AND IDENTIFIED TO REWAIN SHALL BE PROTECTED DURING CONSTRUCTION. SEE LANDSCAPE PLANS FOR SPECIFIE THEE IMPORMATION:

All sanitary sewer construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois", latest edition, and revisions thereto, the notes and on the plans, and in accordance with codes and ordinances of the Village of

STANDARDS FOR SANITARY SEWER CONSTRUCTION

(VILLAGE OF HAMPSHIRE)

- Sanitary sewers and sewer service shall be constructed of the following
  - Polyvinyl chloride plastic gravity sewer pipe (PVC) conforming to ASTM Designation D-3034 or D-2241 with elastomeric gasket joints conforming to ASTM Designation D-3139. The Standard Dimension Raţio (SDR) for PVC pipe shall be 26 as a minimum and shall be dependent on the depth of cover. SDR 26 gravity sewer shall be used for depths up to fifteen (15) feet as measured from the top of the pipe. From fifteen (15) to twenty (20) feet SDR 21 pressure-rated pipe conforming to ASTM D-2241 shall be used. At depths greater than twenty (20) feet, PVC pressure-rated pipe shall be used that has a minimum dimension ratio (DR) of 18 and conforms to ASTM D-2241, AWWA C900 or AWWA C 905, whichever is applicable
  - Where ductile iron sanitary sewer pipe is shown on the plans, said pipe shall be ductile iron pipe, class 52, conforming to AWWA C-151 (ANSI 21.51), with joints complying with AWWA C-111 (ANSI A21.11).
- Pipe size shall be a minimum of 8" for sewer mains and 6" for sewer services. Pipe slopes shall be a minimum of 0.40% for 8" sewer and 1 00% for 6" sewer services.
- All sanitary sewer manholes shall be precast reinforced concrete ASTM designation C-478 provided with approved cast in place rubber boots (flexible manhole sleeve) having a nominal wall thickness of three/sixteenths (3/16) inches with a ribbed concrete configuration and with stainless steel binding straps properly sized. All sanitary sewer manholes shall be set in Butyl rope joint sealant, including all component parts, bottoms, barrels, adjusting rings and castings. The outside joints shall be provided with a four (4) inch wide strip of Butyl-Resin Sealant completely around each joint with vertical lap of one (1) inch and horizontal lap of six (6) inches.
- All manhole covers shall have "Sanitary" cast into the top and shall be the concealed pickhole type. All covers used for sanitary sewers shall have a machined surface and a watertight rubber gasket seal. All manhole frames shall be set with Butyl rope joint sealant. Frame and lid shall be Neenah R-1713 with Type B lid or equal.
- A 4' diameter (min.) Inspection manhole shall be constructed outside all buildings for the purpose of flow monitoring. Said manholes shall provide a minimum 6-inch drop from inlet to outlet pipe to facilitate
- 7. All final adjustments of castings will be accomplished by the use of precast concrete adjusting rings set in Butyl rope joint sealant, mortar joints will not be allowed. Total height of adjusting rings used shall not exceed eight (8") inches. No more than 2 adjusting rings shall be used.
- "SurSeal" chimney seals as distributed by Marathon Materials, Inc. (800/983-9493) or approved equal, shall be installed on all manholes.
- 9. Sanitary sewer services may be constructed according to the details on
- When connecting to an existing sanitary main when a tee or wye is not provided, an "Inserta Tee" fitting must be installed. The minimum distance between fittings is 4 feet center to center. Disruption of any existing sanitary main by breaking or cutting in a wye/tee is prohibited unless the existing main is cracked or broken at the point of connection with "Inserta Tee". A representative of the Village shall determine the existing main repair or replacement required on a case by case basis prior to connection, construction or installation.
- Infiltration leakage shall not exceed 200 gallons per inch of pipe diameter per mile per day of sewer pipe, including manholes in the test
- 12. All sanitary sewers will be subject to an air exfiltration test, televising test, and deflection test to be performed by the Contractor under the supervision of the Engineer. All testing will be done in conformance with the "Standard Specifications for Water and Sewer Main Construction in Illinois". current edition and Village of Hampshire requirements. In addition all manholes shall be vacuum tested.
- Vacuum testing of each manhole shall be carried out immediately after assembly and prior to backfilling. All lift holes shall be plugged with an approved non-shrink grout.

No grout will be placed in the horizontal joints before testing. All pipes entering the manhole shall be plugged, taking care to securely brace the plugs from being drawn into the manhole.

The test head shall be placed at the inside of the top of the frame section and the seal inflated in accordance with the manufacturer's

A vacuum of 10 inches of mercury shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to 9 inches. The manhole shall pass of the time is greater than 60 seconds for a 48" diameter manhole, 75 seconds for a 60" manhole and 90 seconds for a 72" inch manhole.

If the manhole fails the initial test, necessary repairs shall be made with a non-shrink grout while the vacuum is still being drawn. Retesting shall proceed until a satisfactory test is obtained

STANDARDS FOR SANITARY SEWER SERVICE CONSTRUCTION (VILLAGE OF HAMPSHIRE) All sanitary sewer construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois." latest

- edition, and revisions thereto, the notes on the plans, and in accordance with codes and ordinances of the Village of Hampshire, Illinois. 2. Sanitary sewers and sewer services shall be constructed of the following
- Polyvinyl chloride plastic gravity sewer (PVC) conforming to ASTM Designation D-3034 or D-2241 with elastomeric gasket joints conforming to ASTM Designation D-3139. The Standard Dimension Ration (SDR) for PVC pipe shall be 26 as a minimum and shall be dependent on the depth of cover. SDR 26 gravity sewer shall be used for depths up to fifteen (15) as measured from the top of pipe. From fifteen (15) to twenty (20) feet, SDR 21 pressure rated pope conforming to ASTM D-2241 shall be used. At depths greater than twenty (20) feet, PVC pressure rated pipe shall be used having a minimum dimension ration (DR) of 18 and conforming to ASTM D-2241, AWWA C-900, or AWWA c-905, whichever is applicable.
- b. Where ductile iron sanitary sewer pipe is shown on the plans, said pipe shall be ductile iron pipe, class 52, conforming to AWWA c-141 (ANSI A21.51), with joints complying with AWWA C-111 (ANSI A21.11).
- 3. Pipe size shall be a minimum of 6" for sewer services. Pipe slopes shall be a
- 4. Sanitary sewer services may be constructed according to the details on the
- 5. Infiltration leakage shall not exceed 200 gallons per inch of pipe diameter per mile per day of sewer pipe, including manholes in the test section
- 6. When connection to an existing sanitary main when a tee or wye is not provided, an "Inserta Tee" fitting must be installed. The minimum distance between fittings is 4 foot center to center. Disruption of any existing sanitary main by breaking or cutting in a wye / tee is prohibited unless the existing main is broken or cracked at the point of connection with "Inserta Tee." A representative of the Village shall determine the existing main repair or replacement required on a case by case basis prior to construction or installation.

## STORM SEWER NOTES

## 1. GENERAL:

ALL STORM SENER PIPE SHALL BE RCP. UNLESS OTHERWISE NOTED ON THE PLANS. IN ACCORDANCE WITH THE FOLLOWING:

PLAN CODE: MITERIAL

PLP: REINFORCE CONCRETE PIPE LASIM (-15: WITH D-PING GASETED JOINTS, LASIM (-443): TIPE I. CLASS IV, REF
SSRES SECTION 603. ELLIPITEAL RECP PIPE SHALL BE THEF I. HE-II) PER SSRES SECTION 511. PRECAST FLARED END
SECTION, MAI HAVE MASTIL (JOINTS, PAINENTS SHALL BE MADE AT THE CONTRACT UNIT PRICE PER LINEAR FOOT
OF STROM SYMMET COMPLETE IN PLACE.

DIP: DUCTILE IRON WATERMAIN QUALITY PIPE CLASS SZ (AMS) 21.51) WITH MECHANICAL OP PUSH-ON JOINTS (AMS) 21.11.
CEMENT LINING 15 NOT REQUIRED.

PVC: POLYVINYL CHLORIDE SEWER PIPE. SOR 26, CONFORMING TO ASIM 0-3034 WITH ASTM 0-3212 PUSH-ON GASKETED JOINTS. HOPE: HICH DENSITY POLYETHYLENE CORRULATED PIPE WITH SWOOTH INTERIOR MEETING AASHID M-294 SUCH AS ADS N-12 BY ADVANCED DRAINAGE SYSTEM. COLUMBUS. OH: DR HI-O BY HANCOY. FINDLEY. OH. JOINTS SHALL BE SPILL CORRULATED ABANDS BY THE PIPE MANUFACTURER.

UD: RIGID. PERFORATED PVC UNDERDRAIN PIPE (ASTM 0-2729). SOR 35. DR SCHEDULE 40. WITH SOLVENT WELD JOINTS AND FILTER FABRIC WHAPPING OR SDCK. PERFORATED HOPE PIPE AS OLD ACCEPTAGE.

- "BAND SEAL" OR SIMILAR COUPLINGS SHALL BE USED WHEN JOINING SEMER PIPES OF DISSINILAR MATERIALS.
  "BAND SEAL". "FERNOO". AND "MISSION" TYPE COUPLINGS SHALL NOT BE USED ON SEWER MAINS. CHANGES
  IN PIPE MATERIAL SHALL BE MADE AT A STRUCTURE.
- ALL STORM SEMERS ARE TO BE CONSTRUCTED USING A LASER INSTRUMENT TO MAINTAIN LINE AND GRADE.
- ALL FOOTING ORAIN AND SUMP PUMP DISCHARGE PIPES SHALL BE CONNECTED TO THE STORM SEMER SYSTEM, DOWNSPOUTS SHALL DISCHARGE TO THE GROUND.
- THE CONTRACTOR SHALL MAINTAIN AT LEAST THREE 13'1 FEET OF COVER OVER THE 10P OF SHALLOW PIPES AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL MOUND OVER ANY PIPES WHICH HAVE LESS THAN THREE 13'1 FEET OF COVER DURING CONSTRUCTION INTIL THE APPEALS FINAN GRANGE OR PAGE.

## BEDD ING:

A. ALL STORM SENIES SHALL BE INSTALLED ON A TIPE & REMULAR BEDDING, 1/4" TO 3/4"

IN SIZE (CA. 5) A TIPE, AN INNUMENTALIZATES COULD IN A "FIRE DUSTRO DIAMETER OF THE SENIES PIPE BUT NOT

LESS THAN 4", BLOCKING OF ANY KIND FOR CRADE IS NOT PERMITTION. THE RESUME WITERIALS SHALL BE
COMPARIZED TO 90 OF WINDELED PROCTOR DESIGN.TY. BEDDING SHALL EXTROL OT THE SEPHICAL BED AND LIKE PROPERLY OF THE AND DIP PIPE. GOSTOR SHALL EXTROL OT THE SEPHICAL BEDDING SHALL BE CONSIDERED

INCIDENTAL TO THE COST OF PIPE. NO SEPRIFIC PROVENTS HAVE BE MODE FOR THIS OF THE COST OF BEDDING SHALL BE CONSIDERED.

- B. A CONCRETE BENCH TO DIRECT FLOWS SHALL BE CONSTRUCTED IN THE BOTTOM OF ALL INLETS AND WANHOLES.
- THE FRAME, GRATE, AND/OR CLOSED LID SHALL BE CAST IRON OF THE STYLE SHOWN ON THE PLANS.
- MANHOLE LIDS SHALL BE MACHINE SURFACED. NON-ROCKING DESIGN. THE CLOSED LIDS SHALL HAVE THE WORD "STORM" CAST ON THE LID. THE JUDIN'S BETWEEN FORCETE SECTION ADJUSTING RINGS, AND FRAME SHALL BE SEALED WITH A MASTIC COMPOUND.

## 5. CASTINGS:

A. CASTINGS FOR SENER OR OTHER STRUCTURES SHALL BE "NEEMAH" OR APPROVED EQUAL. COST OF CASTINGS SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE STRUCTURE. NO SEPARATE PAYMENT SHALL BE MADE FOR THIS ITEM.

A. THE STORM SEWER SYSTEM SHALL BE THOROUGHLY CLEANED PRIOR TO FINAL INSPECTION AND TESTING.

## . TELEVISING

A. THE STORM SEWER SYSTEM SHALL BE TELEVISED IF REDUIRED BY MUNICIPALITY.

AT CENTER

DRIVE EXTENSION GROVE BUSINESS HAMPSHIRE, ILLINOIS SPECIFICATIONS RYAN I

0366SPEC01.D

9/26/18

SP1

N:Projects\10366\ENG - ROADWAY\103668PEC01-RD.dgn Default User -bbarker

COLOR, WIDTH, STYLE, AND SIZE OF ALL MARKINGS SHALL BE IN ACCORDANCE WITH (MUTCH) EXCEPT AS MODIFIED BY THE PLANS. THERMOPLASTIC MARKINGS SHALL BE INSTALLED WHEN THE PAYEMENT TEMPERATURE IS 55° F AND RISING. PAINT MARKINGS MAY BE INSTALLED WHEN THE AIR TEMPERATURE IS 50° F AND RISING.

## STANDARDS FOR WATER MAIN CONSTRUCTION (VILLAGE OF HAMPSHIRE)

- All water main construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois", latest edition, and revisions thereto, these improvement plans and details, special provisions and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- All water main shall be Ductile Iron Pipe Class 52 with either mechanical or push-on joints and shall conform to ANSI A21.51-96, AWWA C151 and ANSI A21.11-00, AWWA C111.
- All fittings shall be Compact Ductile Iron and shall conform to AWWA/ANSI C153/A21.53-00. Fittings shall be U.L. Listed Class 350, Tyler, Griffin or approved equal.
- All pipe and fittings shall be cement lined in accordance with AWWA/ANSI C104/A21.4-95.
- All fittings shall be mechanical joint and shall be restrained with Mega Lugs by Ebaa Iron unless
- Long radius curves, either horizontal or vertical, may be laid with standard pipe by deflections at the joints. Maximum deflections at pipe joints and laying radius for the various pipe lengths shall Long rations curves, either norizontal or venical, may be tall with standard pure by oritecturis of the joints. Maximum deflections at pipe joints and laying radius for the vanous pipe lengths shall be in accordance with AVWA C800-99. When rubber gasketed pipe is laid on a curve, the pipe shall be jointed in a straight alignment and then deflected to the curved alignment. Trenches shall be made wider on curves for this purpose.
- Sleeves shall be Smith Blair Omni-Coupling #441 or equal. Sleeves shall be provided at locations shown on the plans or as required. The cost of sleeves is considered as incidental to the cost of
- All gate valves shall have a non-rising stem, shall have a standard 2° square operating nut and shall open in a counter-clockwise direction. Gate valves shall be Mueller Resilient Wedge Gate Valve Cat. No. A-2360-23 in accordance with AWWA C-509-01. Main line valves shall be furnished with mechanical joint connections and restrained with Mega Lugs.
- All Valve Boxes shall be cast iron, two piece 5 1/4-inch shafts, Screw-type Tyler Model 666-S. Lids to be marked "Water" (valve box extensions if required are considered in will be equipped with a rubber stabilizer manufactured by Adapter, Inc.
- All hydrants shall be in accordance with AWWA C502-94 and shall be a Mueller A423 Super Centurion hydrant (break away style traffic design) with one 4 1/2" steamer nozzle and two (2) hose outlets, of which the threads conform with the standards of the Village of Hampshire, Illinois. The connections between the main line swivel tee to auxiliary valve and auxiliary valve to hydrant shall be swivel anchor couplings.
- All pressure taps to an existing village main shall be made with Mueller Mechanical Joint Tapping Sleeve No. H615 and Mueller T2360 Flg x MJ Resilient Wedge Tapping Valve. All should be
- All tees, bends, valves, and fire hydrants shall be adequately supported with a concrete base, and supported laterally with poured in place thrust blocking against undisturbed earth for all water main with a diameter 16" and greater. Concrete block may be used in lieu of poured in place thrust blocking for all water main with a diameter less than 16".
- All water mains shall have a minimum depth of cover of 5.5' or as noted on plans.
- 14 All water services shall be type "K" copper pipe with compression connections.
- All corporation stops shall be Mueller. (1" H15008) (1-1/2" & 2" H15013)
- All curb stops shall be Mueller Minneapolis Pattern. (1" H15155) (1-1/2" & 2" B25155)
- All curb boxes shall be Mueller Minneapolis Pattern Base Curb Box. (6' H10300 tapt 2)
- Hydrostatic Tests The Contractor shall perform Hydrostatic Tests in accordance with Division IV. Section 41 of the Standard Specifications for Water and Sewer Main Construction in Illinois, latest edition, and applicable provisions of AWWA C-600 and C-603. The water mains shall be pressure tested at 150 pst. The test pressure shall not drop more than 2 pst for the duration of the test. The gauge shall be of good quality and condition, and be fluid filled. The gauge shall have a large enough range for the pressure being tested and shall be capable of reading a minimum pressure increment of 2 pst. Allowable leakage shall be as set forth in AWWA C-600 latest edition. The testing length shall be limited to 1000 foot. If more than 1000 foot of waterman is tested, the allowable leakage will be based upon 1000 foot. The duration of the test shall be for two hours minimum.
- Disinfection of the Water Mains Upon completion of the newly laid water mains (and water service lines 4" and larger), the water mains shall be disinfected in accordance with the American Water Works Association, Procedure Designation, AWWA C-651, latest edition. The Contractor is responsible for collecting samples and having bacterfological testing performed as required by the IEFA. The Contractor shall furnish to the Village the required documentation, test results, etc., required by the IEFA before placing the water mains in service or before opening a water service
- 20. All water mains and water service lines shall be protected from sanitary sewers, storm sewers, combined sewers, house sewer service connections and drains in accordance with <u>Talle 35</u>: Environmental Protection Agency subtitle F. Public Water Supplies, Chapter II; Environmental Protection Agency, Parts 651-654 Technical Policy Statements, Section 653.119.
- 21. No water service taps shall be made prior to Village receiving the IEPA operating permit.

## STANDARDS FOR WATER MAIN SERVICE CONSTRUCTION

- STANDARDS FOR WATER MAIN SERVICE CONSTRUCTION

  (VILLAGE OF HAMPSHIRE)

  All water main construction shall be in accordance with the "Standard Specifications for Water and Sewer

  Main Construction in Illinois", lasts didino, and revisions thereto, these improvement plans and details, special provisions and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- All water services shall have a minimum depth of cover of 5.5' or as noted on plans.
- All water services shall be type "K" copper pipe with compression connections.
- 4 All corporation stops shall be Mueller. (1" H15008) (1-1/2" & 2" H15013)
- All curb stops shall be Mueller Minneapolis Pattern. (1" H15155) (1-1/2" & 2" B25155) All curb boxes shall be Mueller Minneapolis Pattern Base Curb Box. (6' H10300 tapt 2)
- All water mains and water service lines shall be protected from sanitary sewers, storm sewers, combined sewers, house sewer service connections and drains in accordance with Title 35: Environmental Protection Agency Subtilis F. Public Water Supplies, Chapter II; Environmental Protection Agency, Parts 55:1654 Tachracal Policy Statements. Section 853.119.

## AWWA STANDARD 651-05 SECTION 4.7: DISINFECTION PROCEDURES WHEN CUTTING INTO OR REPAIRING EXISTING MAINS

The following procedures apply primarily when existing mains are wholly or partially dewatered. After the appropriate procedures have been completed, the existing main may be returned to service prior to completion of bacteriological testing in order to minimize the time customers are out of water. Leaks or breaks that are repaired with clamping devices while the mains remain full of pressurized water may present little danger of contamination and therefore may not require disinfection.

## Sec. 4.7.1 Trench Treatment

When an existing main is opened, either by accident or by design, the excavation will likely be wet and may be badly contaminated from nearby sewers. Liberal quantities of hypochlorite applied to open trench areas will lessen the danger from this pollution. Tablets have the advantage in this situation, because they dissolve slowly and continue to release hypochlorite as water is pumped from the excavation.

## Sec. 4.7.2 Swabbing With Hypochlorite Solution

The interior of pipe and fittings (particularly couplings and sleeves) used in making the repair shall be swabbed or sprayed with a 1 percent hypochlorite solution before they are installed.

Thorough flushing is the most practical means of removing contamination introduced during repairs. If valve and hydrant locations permit, flushing toward the work location from both directions is recommended. Flushing shall be started as soon as the repairs are completed and shall be continued until discolored water is eliminated.

Where practical, in addition to the procedures previously described, the section of the main in which the break is located shall be isolated, all service connections shut off, and the section flushed and chlorinated as described in Sec. 4.4.4. The dose may be increased to as much as 300 mg/L and the contact time reduced to as little as 15 min. After chlorination, flushing shall be resumed and continued until discolored water is eliminated and the chlorine concentration in the water exiting the main is no higher than the prevailing water in the distribution system or that which is acceptable for domestic use.

## Sec. 4.7.5 Bacteriological Samples

Bacteriological samples following procedures in 5.1.3 shall be taken after repairs are completed Bacteriological samples following procedures in 5.1.3 shall be taken arter repairs are completed to provide a record for determining the procedure's effectiveness. If the direction of flow is unknown, then samples shall be taken on each side of the main break. If positive bacteriological samples are recorded, then the situation shall be evaluated by the purchaser who can determine corrective action. Daily sampling shall be continued until two consecutive negative samples are recorded.

A CE DRIVE EXTENSION AS GROVE BUSINESS (HAMBERIGE IL INDIES RYAN DE HAMPSHIRE



FILENAME 10366SPEC02.D

9/26/18

SP2

- A. The following is a description of the nature of the construction activity: Construction of a roadway extension.
- 8. The following is a description of the intended sequence of construction activities which will disturb soils for major portions of the construction site:

Describe proposed construction sequence, sample follows:

- Il Install perimeter sediment control measures
  a) Selective vegetation removal for silt fence installation
  b) Silt fence installation
  c) Construction fencing around areas not to be disturbed
  d) Stabilized construction antronce

- al Stabilized construction entronce [Lear and grob (los necessors)] Strip toposil: stockpile topscil and grade site |ampoorally stabilize topscil stockpiles (seed and sitt fence ground foo of slope) |ampoorally stabilized topscil stabilized topscil stabilized to stabi
- 8) Install record in several s
- C. The site has a total acreage of approximately 2.9 acres. Construction activity will disturb approximately 2.9 acres of the site.
- 0. 1) An estimated runoff coefficient of the site after construction activities are completed is 0.90.
- Refer to Sheets (BBLSS.).PP1 for a site plan indicating:
  11 drainage patternal:
  12 approximate slapes anticipated before and ofter rajor grading activities:
  13 locations where webicles enter or exit the site and controls to minimize off-site sediment tracking:
  14 ares of solid (sturburbertural and most implication profit of site sediment):
  15 the location of areas where stabilization practices are expected to occur:
  11 surface waters (including vertication):
  18 locations where storm water is discharged to a surface water.

- 1) The name of the receiving water(s) islares: Wigmayer Road Oitch.
  2) The name of the ultimate receiving water is: Coon Creak.
  3) The extent of wetland acreage at the site is 0.00 acres.
- G. Potential sources of pollution associated with this construction activity may include:
   sediment from disturbed soils
   otherwises
   for

- delegates dele

This section of the SSSE Plan addresses the various controls that should be implemented for each of the major construction cartivities described in the "Site Description" section, for each secure Identified in the major construction control of the Identified State of the Identified State of the Identified State of the Identified State of the regular to Signal acopy of the cartification statement from SPATE INF. at the Identified State of the Part IV.6. - Signatory Requirements, of the Identified State of the Identified State of the Identification statement should be enabled to SIMPP.

The management procisions controls and other provisions contained in the SMPPP should be at least as protective as the requirements controlled in the Illinois Environmental Protection Agency's IEEPA and the United States Department of Agriculture's Natural Resource Conservation Service Illinois Union Manual, 2002. Requirements specified in sadiment and erosion control site plans or site permits on storm water management site plans or site permits approved by local officials that are applicable to protecting surface water resources are using submitted and applicable to protecting surface water resources are using submitted or enforceable under the ILRIO permit even if they are not specifically included in a SMPPP required under the ILRIO permit leven if they are not specifically included in a SMPPP required under the ILRIO permit ones not specifically included in a SMPPP required under the guidelines or technical guidelines do comments that are not identified in a specific plan or permit that is issued for the construction site.

The soil erosion and sediment control measures for this site should meet the requirements of the following agencies:

- Village of Hampshire Kone County IEPA
- B. Control Implementation Schedule

Best Management Practices will be implemented on an as-needed basis to protect water quality. Perimeter controls of the site should be installed prior to sail disturbance teaching poil disturbance necessary to install the controls including denies. Perimeter corrorlas, including the still frace, should be carried by antichlade until fine including sediment into activities. Perimeter corrorlas, including the still frace, should be carried by antichlade until fine sediment traps should be installed as described in the intended sequence of construction activities. The contractor is responsible for the adequate protection including sediment control of existing sewers and seven structures during construction aperations. As necessary, the appropriate sediment control measure should be installed prior to land disturbing activities.

Stabilization measures should be initiated where construction activities have temporarily or permanently cossed, in accordance with Local and State requirements, as described below. Once construction activity in an area has permanently esceed, that one should be permanently stabilized. Temporary perimber controls should be removed after final stabilization of those portions of the site upward of the perimeter control.

C. Erosion and Sediment Controls

The appropriate soil erosion and sediment controls should be implemented on site and should be madified to reflect the current phase of construction. All temporary sediment and erosion control measures should be repoired or replaced as soon as practicable to maintain APPS compliance. Permittee or an outhorized applit is responsible for inspecting all sediment and erosion control measures at a minimum of every? calendor days and within 24 hours of the end of a 0.5-inch or greater! rain event or saveful eguivalent.

Unless otherwise indicated, all vegetative and structural erasion and sediment control practices should be installed to the Stendard Practice. The contractor is responsible for the installation of any additional erasion and sediment control resources descently to minimize a radio and sedimentation as determined by the Uniquineer or Princery Contact.

1) Stabilization Practices - Areas that will not be paved or covered with non-erosive material should be stabilized asing procedures in substantial conformance with the Illinois whom Navoul. This SISE Plan includes a leaded for determined by the Engineer or Primary Confocultional enables controls should be implemented as measuremy.

The following temporary and permanent stabilization practices, at a minimum, are proposed:

Site-specific scheduling of the implementation of these practices is included in the Soil Protection Chart. A record of the dates when major grading activities occur, when construction activities cause on a partial of the site, and when stabilization measures are initiated should be included in the SMPPP.

Except as provided in paragraphs (a) and (b) below, stabilization measures shall be initiated as soon as practicable on particus of the site where construction activities have temporally or permanently accessed, but in no case more than 18 days after the construction activity on that portion of the site has temporally or permanently accessed.

la! Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.

thi there construction opticity will resume on a pertion of the site within 21 days from when opticities cossed. lag., the fold it may period that construction on chirvity is temporarily cased is lass than 21 days then stobilization recurses do not have to be initiated on that portion of site by the lath day after construction optivity temporarily cossed.

2) Structural Proctices - Provided below is a description of structural practices that should be implemented to the degree attainable to divert if lows from exposed soils, store flows or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Structural practices should be placed on uplands soils to the degree attainable, the installation of the following devices may be subject to Section 404 or the Clean Mater Act:

Provided below is a description of measures that will be installed during the construction process to control the pollutaris in starm water discharges that will occur after the construction operations have been completed. The installation of these devices any be subject to Saction 480 of the Clean Noter Act.

1) The practices selected for implementation were determined on the basis of technical guidance contained in 1994's Illinois Broam Mahwal, Federal, State, and/or Local Requirements. The starm water management amounts included.

detention basins (existing wet basin)

2) Velocity dissipation devices such as rib-rop corons at flared and sections or level spreaders, shall be place at discharge locations and along the length of any outfall channel as necessary to provide a non-enable velocity flow from the structure to a velocity and the natural sylviscal, and biological characteristics and function are provided and protected te.g., administration of control training and provided and hydrodynami present prior to the infliction of construction activities!

E. Waste Wonogement
Solid waste moher last including trash. construction debris, excess construction materials, machinery, tools and other
items will be collected and disposed of off site by the contractor. The contractor is responsible to acquire the permit
required for such disposal. Burning on site will not be permitted. No solid materials, including building naterials
shall be discharged to Waters of the Stote, except as anthorized by a Section 404 permit. All waste materials should be
collected and stored in approved receptorles, No wastes should be placed in any location after than in the approved
containers appropriate for the materials being disported. There should be no liquid wastes deposited into dumpsters or
other containers which may leak. Receptorles with deficiencies should be replaced as soon as possible and the appropriate
clear-up procedure should take place. If thecessory, Construction waste material is not to be buried on site. Maste
disposal should comply with all Local. States and feeder lenguistions.

Concrete Waste Managemen

Concrete waste or wishout should not be allowed in the street or allowed to reach a storm water drainage system or watercourse. When practicopie, a sign should be posted at each location to identify the washout. To the extent practicopie, concrete washout be closered an example distance from a storm water drainage intel or watercourse, and should be located at least 10 feet behind the curb. If the eachout area is adjacent to a power road, a stocitized entronce that meets 11 liminal known Marcul standards should be installed of each sobolar area.

The containment facilities should be of sufficient values to completely contain all Figuid and contrate waste materials including enough capacity for anticipated levels of rainwater. The dried concrete waste material should be picked up and alsosted of properly when 15 copacity is readead. Indicement concrete can be organly recycled and used again on site tab approved by the Engineer or hould off site to an appropriate familiar.

G. Concrete Cutting

Concrete waste management should be implemented to contain and dispose of sow-cutting slurries. Concrete cutting should not take place during or immediately after a rainfall event. Moste generated from concrete cutting should be cleaned-up and disposed into the concrete cutting should be cleaned-up and disposed into the concrete washout facility as described above.

H. Vehicle Storage and Maintenance

n. venicle alongue and weintempole
When neil in use, construction which is should be stored in a designated orabial outside of the
regulatory floodblain, dway from any natural or proteid watercourse, pand, drainage-way or storm drain,
controls should be installed to minimize the potential of runnof from the storage areals if from reaching storm
drains or water courses. Which a minimate has potential of runnof from the storage areals if from reaching storm
drains or water courses. Which a designated arous) is prevent the migration of depoting of the consistence of the should be made within a designated arous) in prevent the migration of depoting of the following the consistency of the cons

I. Waterial Storage and Good Housekeeping

Meter iols and/or containments should be stored in a manner that minimizes the potential to discharge into store drains or watercourses. An an-site area should be designated for material delivery and storage. All materials kept on site should be stored in their original containers with lagible tabels, and if possible, under a care of the store of their original containers with lagible tabels, and if possible, under a care of a capetable control insource to prevent contained to of store water. MSD should be available to execute the control insource to prevent contained to of store water. MSD should be available to deliver of classical stores. Any release of chemical storeonismins should be immediately clasmed up and disposed of properly. Centractors should immediately report all soils to the Primary Contact, who should notify the oppropriate appreciation.

To reduce the risks associated with hozordous materials on site, hozordous products should be kept in original containers unless they are not re-sealable. The original labels and MSDs should be retained on site at all times. Nacrodous naterials and all other naterial on site should be stored in accordance with mountacturer or MSD specifications. When disposing or hozordous naterials are commended methods.

The following good housekeeping practices should be followed on site during the construction project:

- An effort should be made to store only enough product required to do the job.
- All materials stared on site should be stored in a neat, orderly manner in their appropriate containers and adequately protected from the environment.
- Products should be kept in their original containers with the original manufacturer's label.
- Substances should not be mixed with one another unless recommended by the manufacturer.
- Operations should be observed as necessary to ensure proper use and disposal of materials on site.
- Whenever possible, all of a product should be used up before disposing of the container.
- Manufacturer's recommendations for proper use and disposal should be fallowed.
- J. Management of Portable Sanitary Stations

To the extent procticable, portraits spirity stortions should be located in an area that deas no area to any protected returning storting storting storting stores and the State, or store extent structures and should be unabored for the grant of extent from the joing over. Portfolle Sanitary stortions boarded in impervious surfaces should be placed on top of a secondary containment device, or be surrounded by a control device leg. -great-bag permit. The contractor should not create or allow unabout conditions. Sont large was should be disposed of in accordance with applicable State and/or Local regulations.

K. Spill Prevention and Clean-Up Procedures

Mountacturer's recommended methods for spill clean-up should be available and site personnel should be made owere of the procedures and the location of the information and clean-up supplies. Materials and equipment necessary for spill clean-up should be kept in the material strong one on site. Equipment and materials should include but are not limited to broats dust parts, maps, raps, gloves, goggles. Kithy litter's and, swedst and platfit conformed to the conformation transport conformations are extended to the conformation transport conformation to the conformation transport conformat

Discharges of a hazardous substance or all caused by a spill let.g., a spill of all into a separate storm sever or its dest of the State) are not authorized by the LIRID permit. If a spill occurs, notify the Primary Contact immediately. The construction is site should now the cooper's to control, contain, and remove spills, if they occur. Spills should be cleaned up immediately latter discovery! In accordance with MSS and should not be out-led on site or wisoble into store sever or danger inters. draining-ways, or Maters of the State.

Spills in excess of Federal Reportable Quantities (as established under 40 CFR Parts 110, 117, or 302), should be reported to the Notional Response (enter by calling 1800 424-8802, 1805 often include indramation on Federal Reportable Quantities for materials, Spills of toxic or hazdrads unterials should be reported to the oppropriate State of Cool government agency, as required. When cleaning up a spill, the area displayed with lateral to the propriate State of Cool government agency, as required. When cleaning up a spill, the area displayed with lateral days substance.

In addition to the good housekeeping and other management practices discussed in the previous sections of these Notes, the following minimum practices should be followed to reduce the risk of spills:

- On-site vehicles should be monitored for leaks and should receive regular preventative maintenance to reduce the chance of leakage.
- Contractors should follow the manufacturer's recommendations for prober use, storage, and disposal of materials. Excess materials should be disposed of occording to the manufacturer's instructions or State and Local regulations, and should not be discharged to the starm sever or waterbody.
- L. De-Watering Operations

During de-watering/pumping operations, only uncontaminated water should be allowed to dispharge to protected natural areas. Waters of the State, or to a storm sever system in accordance with Local permits), fallet hoses should be placed in a stabilized sump pit or floated at the surface of the water in order to limit the anopun to facilities. Pumping operations way be discharged to a stabilized area that consists of an energy dissipating device (e.g., store), sediment filter bag, or both. Adequate erosion controls should be used our ingle-watering operations as necessary. Stabilized conveyance channels should be installed to direct water to the desired logation as applicable.

M. Off-Site Vehicle Tracking

The site should have one or more stabilized construction entrances in conformance with the Plan details. Stabilized construction entrances is should be installed to help reduce vehicle tracking of sediments. Streets should be seen as needed to reduce access sediment, dirt, or state tracted from the site. Mointenance may include to polarising the stabilized entrance with additional stone and removing too layers of stone and sediment, as needed. Vehicles houling arrolls in attail of to and from the construction site should be ownered with a tory.

If toppolities to be stockpiled at the site, select a location so that if will not ende, block drain or interfere with work on site. Toppolities should not be located in the 100-year fiscabolities should not be located in the 100-year fiscabolities should not stock the site of protected with sediment tropping messives. Per interface controls, such as sit fence, should be picced ground the stockpile is mediately. Stock lization of the stockpile is that completed if the stockpile is for semior undisturbed for longer than thirty down.

Dust Control

. MAINTENANCE

just control about se inclemente on site as messary. Sept interirement about se and indica secret to concernition control when temporery dist control measures are seed. A wester trads about se present on site for conditional for sprinkling/irrigation to limit the amount of dust leaving the site. Metering should be applied oilty for more requantly if the defective. Control should be used not to oververer, as that may only

I field observations indicate that additional protection from wind crosson (in addition to, or in place of the control is necessary, alternative dust suppressent controls should be implemented at the discretion and provid of the Cinjense and/or Prisary Control.

Street cleaning should also be used as necessary to control dust. Poved areas that have soil on them from the construction site should be cleaned as needed, utilizing a street sweeper or bucket-type endloader or scroper at the direction of the Engineer and/or Primary Contact.

Maintenance of the controls incorporated into this project should be performed as needed to assure their conti-effectiveness. This includes promot and effective repoir and/or replacement of deficient control measures. I following is a osserption of procedures that should be used to maintain in agood and effective operating come erosion and sediment control measures and other profective measures identified in the SESC Plan and Standard Specifications.

Dust control: When temporary dust control measures are used, repetitive treatment should be applied as needed to

Sediment filter bogs: Sediment filter bogs should be installed on pump outlet hoses that discharge off site or to sansitive on-site creas, and should be placed in an area that allows for the bog to be removed without producing a sediment discharge. The bogs should be inspected frequently and reported or replaced as needed.

Ill fence: Silf fences should be inspected regularly for undercutting where the fence meets the ground, overtagating test along the length of the fence. Deficiencies should be repaired immediately. Retaye accumulates addirents from the fence base when the sediment reaches on-holf the fence height. During final stabilization, properly disposing or any sediment from the social series of the sediment for the social series. Afternative sediment control measures should be considered or draws where stilf fence with fence the sediment control measures should be considered or draws where stilf fence both includy fails.

lamporary sediment trops: lamporary sediment trops should be inspected after each period of significant roin flattive sediment and restore the trop to its original dimensions when the sediment has occumulated to one-half its reproduction of the sediment of the sediment

INSPECTIONS he Permittee for their outhorized representativel will be responsible for conducting site inspections, or compliance with the [LR10 MPDS Permit. After each inspection a report should be prepared by the person wherefromed the inspection. The inspection report should be maintained on site is port of the SWPPP.

Inspections should be conducted at least once every seven calendar days and within 24 hours of the end of a storm event that is 0.5 inches or greater, or equivalent showfall.

ach inspection should include the following components:

A. Disturbed cress and pressured for the storage of materials that are exposed to precipitation should be inspected for evidence of or the potential for, petiturants entering the drainage system. The wrold and segligent control insources identified in the segligent source is desired. The control insources identified in the segligent source expected to core consistent they should be inspected to ascertion whether erosion control insources are effective in preventing significant inspects to the receiving vaters. Locations where wholese after one virt has site should be inspected for off-site sediment tracking. All jumping operations and other potential non-store

8. Space on the results of the inspection, the description of potential pollutant sources identified, and the pollution prevention measures described in the SRPP should be revised, as oppropriate, as soon as proficioned offer the inspection. The modifications if any, shall provide for finely implementation of any changes to the SRPPP within 7 colendor days following the inspection.

C. A report summorizing the scope of the inspection, namels and qualifications of personnel making the inspection. The date(s) of the inspection, major observations relating to the implementation of the SMPP, and actions token in accordance with paragraph 8, above should be made and retained as part of the SMPP for at least three years from the date that permit coverage expires or is terminated. The report should be signed in accordance with PRF v16. Signatory Requirements of the LIRTO RMPCS Permit.

b. The Permittee should complete on subsit within 5 days on "Incidence of Non-Central research of the Life when the permittee should complete on subsit within 5 days on "Incidence of Non-Central research of the SMPP observed during on inspection conducted; including those not experited by the SMPP. Submission should be on frome providee by IRP and include aspectific reducts of non-complete or the complete of the Central Research of non-complete, and a strategic detailing any environmental impact, which may have resulted to remember the complete or the concerning times.

All reports of non-compliance shall be signed by a responsible authority as defined in Part VI.G. ignatory Requirements), of the ILRIO MPDES Permit.

All reports of non-compliance shall be mailed to IEPA at the following address:

Illinois Environmental Protection Agency livision of Water Pollution Control compliance Assurance Section 021 North Grand Avenue East ost Office Box 19276 or inglield. Illinois 62794-9276

scept for flows from fire fighting activities, possible sources of non-storm water that may be combined with form water discharges associated with the proposed activity, are described below:

- Water used to wash vehicles where detergents are not used:
  Nater used to control dust:
  Nater used to control dust:
  Properent wash waters where spills or leaks of towic or hazardous materials have not occurred (unless spilled materials have been removed) and where detergents are not used;
  Irrigation distructs:
- Intiguities actions of the property of the property of the process materials such as solvents. Foundation or faoting drains where flows are not contaminated with process materials such as solvents.
- ollution prevention measures should be implemented for non-storm water components of the discharge.

STABILIZATION TYPE	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	ост.	NOV.	DEC
PERMANENT SEEDING		-2318790	+A						-			
DORMANT SEEDING	В		-								+B	_
TEMPORARY SEEDING			+c			-	, D		-			
SODDING			,E**						_			
MULCHING	F											

KENTUCKY BLUEGRASS 90 LBS/ACRE MIXED WITH PERENNIAL RYEGRASS 30 LBS/ACRE

D WHEAT OR CEREAL RYE 150 LBS/ACRE.

C SPRING DATS 100 LBS/ACRE

30 LBS/AURE.

8 KENTUCKY DULEDRASS 135 LBS/ACRE 150 LBS/ACRE E SOD
45 LBS/ACRE + STRAW MULCH 2 TONS/ACRE.

F STRAW MULCH 2 TONS/ACRE.

* IRRIGATION NEEDED DURING JUNE AND JULY.
** IRRIGATION NEEDED FOR 2 TO 3 WEEKS AFTER APPLYING SOD.

SOIL PROTECTION CHART

PROJECT: RYAN DRIVE EXTENSION AT HAMPSHIRE GROVE BUSINESS CENTER PERMIT #: ILR10 TELEPHONE NUMBER CONTRACTOR SIGNATURE PRINTED NAME & TITLE NAME OF CONTRACTING FIRM STREET ADDRESS CLTY, STATE, 71P CDDE

NOTE: ALL CONTRACTORS PERFORMING WORK ON THIS SITE ARE REQUIRED TO SIGN A CONTRACTOR CERTIFICATION STATEMENT AS ILLUSTRATED ABOVE. THE SIGNED STATEMENTS WILL BE MAINTAINED ON THE SITE WITH THE SWPPP

DWNER SWPPP CERTIFICATION

PROJECT: RYAN DRIVE EXTENSION AT HAMPSHIRE GROVE BUSINESS CENTER

PERMIT #: ILR10 ____

I CERTIFY LANGER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED LANGER WE DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT OWN LIFTED PREPARED AND PRIVATE THE INFORMATION SUBJECTED RESIDENCE TO ASSURE THAT OWN LIFTED WERE THE RESIDENCE OF THE PROPERTY O

STONATURE OF OWNER

PRINTED NAME OF DWINER

NOTE: THE CERTIFICATION ILLUSTRATED ABOVE SHALL BE SIGNED BY THE DWARE LISTED ON THE MOTICE OF INTENT IN ACCORDANCE WITH PART VI.C. OF THE ILRID NODES PERMIT. THE SIGNED STATEMENT SHALL BE MAINTAINED ON THE SITE WITH THE SWPPP.


DATE


R POLLUTION PREVENTION PLAN
DRIVE EXTENSION AT
E GROVE BUSINESS CENTER
HAMPSHIRE, ILLINOIS STORMWATER IN BRAIN DIN BRAINE COMMENTER IN THE COMMENT OF THE COM


10366SE01


09/26/18 JOB NO.


> SE1 9 OF 1
















SOIL EROSION AND SEDIMENT CONTROL PLAN
RYAN DRIVE EXTENSION AT
HAMPSHIRE GROVE BUSINESS CENTER
HAMPSHIRE. ILLINOIS

SITE DEVELOPMENT ENGINEERS LAND SURVEYORS 575 W. Higgins Road, Suite 700.


[LAND SURVEYO 9575 W. Higgins Road Rosemont. Phone: [847] 696 4060 Fax; [8





FILENAME: 10366SE02.DGN

DATE: 09/26/18 JOB NO. 10366

**SE2** 









TO BE USED WHERE EXISTING UTILITY LINE CANNOT BE MOVED OR EXISTING WATER MAIN MUST BE RELOCATED TO ALLOW NEW UTILITY LINE TO BE CONSTRUCTED.

WATER MAIN OFF-SET DETAIL




TYPICAL SECTION THRUST BLOCKS




NOTE:

2. ALL JOINTS ARE TO BE THEKPOINT WITH HYDRAUDIC CEMENT

TYPICAL PRESSURE CONNECTION IN VALVE VAULT





AT CENTER DETAILS - 2


DRIVE EXTENSION AS GROVE BUSINESS (HAMPSHIRE ILLINOLG) RYAN I

10366DET02.DGN


09/26/18 JOB NO. 0366

D2 13 OF 14

VProjects\10366\ENG - ROADWAY\10366DET02-RD.dgn Default User bbarker



N:Projects\10366ENG - ROADWAY\10366DET03-RD dgn Default User bbarker



SPACECO INC.

AT CENTER

DETAIL 3

DRIVE EXTENSION A

GROVE BUSINESS (
HAMPSHIRE ILLINOIS


RYAN I HAMPSHIRE

FILENAME: 8182DET03.DGN

DATE: 09/26/18

JOB NO. 10366 SHEET

**D3** 



REVISIONS BY

Dowden Landscape Design

P.O.Box 415, Libertyville, Phone: (847) 362~1



PLAN LANDSCAPE HAMPSHIRE

PARK

RYAN DRIVE GROVE BUSINESS

Date 69.27.18


Scale 1"430' Drawn CJD

dob


L - 1.0

## ROADWAY LUMINAIRE SCHEDULE CALLOUT SYMBOL DESCRIPTION MODEL TOTAL VA VOLTS S2 SINGLE HEADED LED SHOE BOX FIXTURES MOUNTED DIST-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE: SSS-25-4C-DW28-PL-DDB DX1-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE: SSS-25-4C-DW28-PL-DDB

PHOTOMET	RIC STATIS	TICS	
FLANNIGAN DRIVE	AVERAGE	MINIMUM	UNIFORMITY RATIO
	1.5fc	0.2fc	7.5:1



1 KEY PLAN
SCALE 1" = 100'-0"





40 S. ADDISON ROAD ADDISON, IL 60101 630-543-9059 www.connellyelectric.com

NORTHERN BUILDERS 5060 RIVER ROAD SCHILLER PARK, IL 60176 847-678-5060



	DATE
ISSUED FOR PERMIT	09/28/2018
	ISSUED FOR PERMIT

## RYAN DRIVE


HAMPSHIRE GROVE BUSINESS CENTER HAMPSHIRE, IL

## ROADWAY PHOTOMETRIC

PROJECT NUMBER	18-0000
DATE	09/28/2018
DRAWN BY	AB
CHECKED BY	JDO

E101

2 ROADWAY PHOTOMETRIC
SCALE 1" = 30'-0"





40 S. ADDISON ROAD ADDISON, IL 60101 630-543-9059 www.connellyelectric.com

NORTHERN BUILDERS 5060 RIVER ROAD SCHILLER PARK, IL 60176 847-678-5060



NO.	DESCRIPTION	DATE
△	ISSUED FOR PERMIT	09/28/2018

## RYAN DRIVE

HAMPSHIRE GROVE BUSINESS CENTER HAMPSHIRE, IL

## ROADWAY LIGHTING PLAN

ROJECT NUMBER	18-0000
DATE	09/28/2018
RAWN BY	AB
HECKED BY	JDO

E102

## PET-AG AT HAMPSHIRE GROVE BUSINESS CENTER

HAMPSHIRE, ILLINOIS

PROJECT NO:10366

## **ARCHITECT**

HARRIS ARCHITECTS, INC. 4801 EMERSON AVENUE, SUITE 210 PALATINE, ILLINOIS 60067 PHONE: 847-303-1155

## **DEVELOPER**

NORTHERN BUILDERS, INC. 5060 RIVER ROAD SCHILLER PARK, IL 60176 PH: 847-678-5060

> CALL J.U.L.I.E. 1-800-892-0123 WITH THE FOLLOWING:

COUNTY KANE

CITY, TOWNSHIP HAMPSHIRE, T42N SEC. & 1/4 SEC. NO. SEC 11 NW 1/4

48 HOURS BEFORE YOU DIG. EXCLUDING SAT., SUN. & HOLIDAYS

		INDEX
SHEET #	SHEET I.D.	SHEET DESCRIPTION
1	C1	COVER SHEET
2	GN	TYPICAL SECTIONS & GENERAL NOTES
3	ET	EXISTING CONDITIONS PLAN
4	GM1	GEOMETRIC PLAN
5	GR1	GRADING PLAN
6	UT1	UTILITY PLAN
7-8	SP1-SP1	SPECIFICATIONS
9-11	SE1-SE3	SOIL EROSION AND SEDIMENT CONTROL PLANS
12-14	D1-D3	DETAILS

## BENCHMARK


FLEVATION:

SEE SHEET GN FOR BENCHMARK INFORMATION

## NOTE:

SPACECO, INC. AND THE VILLAGE ARE TO BE NOTIFIED AT LEAST THREE (3) DAYS PRIOR TO STARTING CONSTRUCTION
AND SHALL BE INCLUDED IN THE PRECONSTRUCTION MEETINGS

## LOCATION MAP



## DRAINAGE CERTIFICATION

REGISTERED PROFESSIONAL ENGINEER

## REVISIONS

ORIGINAL PLAN DATE: SEPTEMBER 26, 2018				118		
#	SHEET	#		REMARK	S	DATE
+						
	-					
				-		
		-				
-						
-						

ENGINEER MICHAEL MONDUS, P.E. ILLINOIS REGISTRATION NO.: 062-052057 EXPIRATION DATE: 11/30/2019

THESE PLANS OR ANY PART THEREOF SHALL BE CONSIDERED VOID WITHOU THE SIGNATURE, SEAL, AND EXPIRATION DATE OF SEAL OF THE ENGINEER

ISSUED FOR REVIEW 09/26/18

PET-AG AT HAMPSHIRE GROVE BUSINESS CENTER HAMPSHIRE, ILLINOIS

Rosemont, Illinois 60018 4060 Fax: (847) 696-4065 Higgins Road, Suite 700, Phone: (847) 696-

9575 W.



0366TITLE

DATE: 09/26/18

JOB NO. 10366

C1

## GENERAL NOTES AND CONSTRUCTION SPECIFICATIONS

- The "Standard Specifications for Road and Bridge Construction" adopted \$981. 1, 2015 the 
  "Standard Specifications for Water and Sewer Main Construction in Illinos", Sixth Edition dated 
  ANNIAN. 1014 and revisions therefor, these improvement plans and details, Special provisions and 
  codes and ordinances of the Willage of Hampshire, Illinois shall govern applicable portions of this
- The Contractor shall obtain, erect, maintain and remove all signs, barricades, flagmen and other control devices as may be necessary for the purpose of regulating, warning or guiding traffic. Placement and maintenance of all traffic control devices shall be in accordance with the icable parts of Article 107.14 of the Standard Specifications, the "Standard Specifications for
- Locations of utilities shown on plans are approximate only, and are not necessarily completed contractor shall make his own investigations as to location of all existing underground structure cables, utilities and pipe lines
- The Contractor shall notify J.U.L.I.E. (1-800-892-0123) at least ten days prior to construction s hat each utility company can stake out any underground improvements that they may have which night interfere with the proposed construction.
- The Contractor shall be required to make arrangements for the proper bracing, shoring and other required protection of all roadways, structures, poles, cables and pipe lines, before construction begins. He shall be responsible for any damage to the streets or roadways and associated structures and shall make repairs as necessary to the satisfaction of the Engineer and Village at
- The Contractor shall be responsible for the protection of all private and public utilities even though they may not be shown on the plans. Any utility that is damaged during construction shall be repaired or replaced to the satisfaction of the Engineer and Wilage by the Contractor at his own
- The Contractor shall examine the plans and specifications, visit the site of the work and inform himself/herself fully with the work involved, general and local conditions, all Federal, State and local laws, ordinances, rules and regulations and all other pertinent items which may affect the cost and time of completion of this project before submitting a proposal.
- All work and materials shall be in accordance with code requirements
- Prior to submitting his pid, the Contractor shall call the attention of the Engineer to any material or equipment he deems inadequate and to any item of work omitted.
- The pay items shall be as noted in the Summary of Quantities/Proposal. Any item of work that is shown on the plans to be performed by the Contractor, for which there is no pay item, shall be considered incidental to the cost of the project.
- Structures for valve vaults for water mains shall be in accordance with the improvement plans and the applicable standard specifications. Where granular trench backfill is required around these structures, the cost shall be considered as incidental and shall be included in the contract unit price for the structure.
- 13. Frame and cover or grates for water main structures shall be as indicated within these
- set in Butyl rope joint sealant; mortar joints will not be allowed. Total height of adjusting rings used shall not exceed eight (8") inches. Cost for adjustment is considered incidental.
- The underground contractor shall be responsible to place on grade and coordinate with other contractors all underground structure frames such as catch basins, inlets, manholes, hydrants, buffalo boxes, valves, etc. No additional compensation shall be paid and said adjustments shall be considered incidental to other items of construction.
- The Contractor shall restore any area disturbed to a condition equal to or better than its original use. This shall include finish grading, establishment of a vegetative cover (seeding or soot), general cleanup and pavement replacement.
- All trenches caused by the construction of sewers, water mains, water service pipes and the excavation around catch basins, manholes, inlets and other appurtenances which occur within the limits of existing or proposed pavements, sidewalks and curb and gutters or where the edge of the trench shall be within two (2) feet of said improvements shall be backfilled with compacted granular trench backfill or with approved suitable select material and properly compacted in accordance with Division II Section 20 of the "Standard Specifications for Water and Sewer Main Construction in Illinois", Sixth Edition, Dated July, 2009, and revisions thereto.

Trench backfill quantities for public utilities and utility conduits have been computed and shall be paid for based on the following maximum trench widths in accordance with Division II of the "Standard Specifications for Water and Seven Man Construction in Illinois", Sixth Edition, Dated July, 2009, and revisions thereto. The depth of backfill shall be measured from the top of pipe embedment to the finished subgrade or as noted on the plans.

Required Trench Width on Each Side of the Pipe

Trench Depth/ Protection

Trench backfill required in excess of the quantity beyond the maximum trench width shall be considered incidental to the contract unless authorized by the Engineer.

- The Contractor shall be responsible for providing safe and healthful working conditions throughout
- The Engineer will be given forty-eight (48) hours notice for any staking that is to be done. Each of the various items of work covered by this contract will be staked once. Additional staking required due to the negligence of the Contractor shall be paid for by the Contractor at the current hourly rate.

- The Contractor shall inform the Village Engineer before work commences on each category of construction, i.e. water main, grading, pavement and drainage inno overent. A twenty-four (24 hour notice shall be given for any item that requires final testing and inspection such as water
- The Engineer will furnish the Contractor with lines and grades necessary to the proper prosecution and control of the work. The Contractor shall call the altention of the Engineer to any errors or discrepancies which may be suspected in lines and grades which are established by the Engineer, and shall not proceed with the work until any lines and grades which are believed to be in error have been verified or corrected by the Engineer or his representative.
- All lot irons damaged or removed during construction of this project shall be replaced by the Engineer and said cost of replacement shall be paid by the Contractor
- Before acceptance by the Village and final payment, all work shall be inspected and approved by the Village Engineer. Final payment shall be made after all of the Contractor's work has been approved and accepted.
- The Contractor will have in his possession on the job site a copy of the plans and specifications
- 25. If any approved equal items are required, the Contractor shall contact the Engineer for approval.
- Any drain and/or field tile encountered by the Contractor during the installation of the improvements shall be returned to original condition. This work to be considered incidental to the contract.
- All road signs, street signs and traffic signs which need to be relocated or moved due to construction shall be taken down and stored by the Contractor at his own expense, except those which are necessary for proper traffic control which shall be temporarily reset until completion of construction operations. After completion of the work, the Contractor shall reset, at his expense.
- The Confractor shall dispose of all excess excavation, unsuitable and unusable materials offsite and at an approved location in a manner that public or private property will not be damaged or endangered. This work is considered as incidental to the cost of the project.
- "Band-Seal" or similar couplings shall be used when joining sewer pipes of dissimilar materials.
- built drawings shall be prepared by the Contractor and submitted to the Engineer as soon as site improvements are completed. Any change in length, location or alignment shall be shown
- The Contractor is responsible for coordinating any required inspections with the Village of
- Special attention is drawn to the fact that Article 105.06 of the standard specifications requires the Contractor to have a competent superintendent on the project site at all times, irrespective of the amount of work sublet. The superintendent shall be capable of reading and understanding plans and specifications, shall have full authority to execute orders to expectite the project, shall be responsible for scheduling and have control of all work as the agent of the Contractor. Failure to comply with this provision will result in a suspension of work as provided in Article 108.07.
- The Engineer and Village are not responsible for the construction means, methods, techniques, sequences or procedures, time of performance, programs or for any safety precautions used by the Contractor. The Contractor is solely responsible for execution of his work in accordance with the contract documents and specifications.



2" HOT MIX ASPHALT SURFACE COURSE, N50
2" HOT MIX ASPHALT BINDER COURSE IL 19.0, N50
BITUMINUS MATERIALS (PRIME COAT)
10" AGGREGATE BASE, CA-6, TYPE A

- COMPACTED SUBGRADE

COMPACTED SUBGRADE

LIGHT DUTY PAVEMENT


STRUCTURAL NUMBER 2" x 0.40=0.80 2" x 0.33=0.66 10"x 0.11=1.10 SN=2.56




2" HOT MIX ASPHALT SURFACE COURSE, N50 4" HOT MIX ASPHALT BINDER COURSE IL 19.0, N50 BITUMINOUS MATERIALS (PRIME COAT)
12" AGGREGATE BASE, CA-6, TYPE A


HEAVY DUTY PAVEMENT

STRUCTURAL NUMBER 2" x 0.40=0.80 4" x 0.33=1.32 12"x 0.11=1.32





TYPICAL SIDEWALK/PEDESTRIAN PATH SECTION



EXISTING		DESCRIPTION	PROPOSED	
		DRAIN TILE		
- >	_>		-))	
>	_>		->>	
»	>>	SANITARY TRUNK SEWER	<del>-&gt;&gt; -&gt;</del>	
w	— B" —			
		PIPE TRENCH BACKFILL	Y040000000	
-G	c_	CAS MAIN	-0	
т		TELEPHONE LINES	-1T	
-E	-3-		-6	
×-		FENCE	x	
		RIGHT-OF-WAY		
		EASEMENT		
		PROPERTY LINE		
		SETBACK LINE		
		CENTERLINE		
680	_	CONTOUR	680	
		SANITARY MANHOLE	0	
Ø ==		STORM MANHOLE	•	
		CATCH BASIN		
		INLET		
		FIRE HYDRANT		
2.73		PRESSURE CONNECTION	(8)	
		PIPE REDUCER	•	
е	0	VALVE AND VAULT, VALVE	9	
		FLARED END SECTION	4	
	_	STREET LIGHT	×	
-0	_	UTILITY POLE	+	
<b>∆</b>		CONTROL POINT	4	
		SIGN		
XXXXX		SPOT ELEVATION	xxx-xx	
<b>D</b>		SOIL BORING	•	
		OVERLAND FLOW ROUTE	->	
		DRAINAGE SLOPE	-~ OR -	
D	0	GUARDRAIL	_ a _ a	
~		WATER'S EDGE	~	
		CONCRETE		
		REVERSE PITCH CURB	прининини	
(·)*	740	TREE, FIR TREE, BUSH, &	X	

## **ABBREVIATIONS**

1 - INVERT OR INLET M . STORM MANHOLE TF - TOP OF FOUNDATION S - SANITARY MANHOLE GF - GARAGE FLOOR

CB - CATCH BASIN LP . LIGHT POLE VV - VALVE VAULT F - FND SECTION

FH - FIRE HYDRANT OP - OUTLET OF PIPE GR - GRADE RING CHYDRANT

IEPA POLLUTION CONTROL

T/P - TOP OF PIPE B/P - BOTTOM OF PIPE WM - WATERMAIN

TC - TOP OF CURB SAN - SANITARY SEWER TD - TOP OF DEPRESSED CURB TW - TOP OF RETAINING WALL BW - BOTTOM OF RETAINING WALL

STM - STORM SEWER LO - LOOK OUT PLO - PARTIAL LOOK OUT

PERMITS PERMIT NO. DATE ISSUED DESCRIPTION LOG NO. 004081618 09/21/2018 IHPA 1901524 08/13/2018 IDNR IFPA NOI IEPA PUBLIC WATER SUPPLY

## CONTACT INFORMATION

VILLAGE ENGINEER

ENGINEERING ENTERPRISES, INC 52 WHEELER ROAD SUGAR GROVE, IL 60554 PH- 630-466-4700 CONTACT: BRAD SANDERSON

## BENCH MARK

SOURCE BENCHMARK, INTOMINE GEODETIC SURVEY MAD TOWN. GEODETIC SURVEY MAD TOWN. GEODETIC SURVEY MAD TO THE MAD THE MAD

KISI PID: NHO213 STATION IS BENCH MARK DISK SET IN TOP OF CONCRETE MONUMENT LOCATED D.9 MI SOUTHEAST FROM HAMPSHIRE. ELEVATION = 919.43 NAVD 88

SITE BENCHMARK *1: BOX CUT AT THE SOUTHWEST CORNER OF CONCRETE PAD FOR STREET LIGHT CONTROL BOX AT NORTHWEST CORNER OF SITE. ELEVATION = 971.38

NOTES GROVE GENERAL AG AT HAMPSHIRE (BUSINESS CENTER HAMPSHIRE ILLINOIS AND SECTIONS PET


CONSULTING ENGIN SITE DEVELOPMENT E LAND SURVEYORS





10366GN.DGN


0366

GN 2 OF









EARTHWORK NOTES	PAVING NOTES
EARTHWORK NOTES  1. GUERAL  1. IT IS THE CONTRACTOR'S REPORDED HE FOR ANY DEPARTMENT OF THE STITE.  4. IT IS THE CONTRACTOR'S REPORDED HE WITHOUT HE A SURFERON HE CONTRACTOR'S GREEN TO ANY DEPARTMENT OF THE STITE AND ANY D	1. SECURE  A. PARADER SERVICIOS FINAL SURGES CONTROL PRIVATE TO ANY CONTROL THEORY OF SOCIETY OF SO
CIONING AND DAUGHGHT HARVING	E. FINAL ACCOMMENT OF THE TOTAL PAYORINT INSTALLATION SHALL BE SUBJECT TO THE TESTING AND EMERCING REQUIREMENTS CITED ABOVE.  TREE PROTECTION
SIGNING AND PAVEMENT MARKING	TREE TROTEOTION
1. ALL SIDNING AND PAVENENT MARKING SHALL BE IN ACCORDANCE WITH THE ILLINDIS MANUAL ON UNIFORM TRAFFIC CONTROL OFFICES HANDOS. THE SIMPARD SPECIFICATIONS FOR PRODU AND BRIDGE CONSTRUCTION ISSRED. MARKING HAND COLOR AND THE FER HANDS.  2. CONTRACTOR SHALL ESTABLISH LOCATION OF ALL SIGNS AND MARKINGS FOR APPOPUAL BY THE DWHEEP PRIOR TO INSTALLATION.  3. SIDNE: SIGNS SHALL BE CONSTRUCTED OF JOBO INDITITION TABLE, WITH REPLECTORIZED LEEKON ON THE FEET WAS COMPANIED AND THE SHOWN OF ACCORDANCE WITH ISSBET INSECTION TO TABLE SHALL BE IN ACCORDANCE WITH WILDO AND AS SHOWN ON THE TEXT WAS COMPANIED BY THE SHOWN OF THE PRIOR OF THE SHOWN OF THE SHALL BE INSECTION TO THE SHOWN OF THE SHALL BE INSECTION TO THE SHOWN OF THE SHALL BE INSECTION TO THE SHAPP OF THE SHALL BE INSECTION TO THE SHAPP OF TH	1. EXISTING TREES IDENTIFIED TO REMAIN SHALL BE PROTECTED OUR NO CONSTRUCTION. SEE LANDSCAPE PLANS FOR SPECIFIC TREE INFORMATION.
R COURS WINTH STYLE AND SIZE OF ALL MARKINGS SHALL RE IN ACCORDANCE WITH (MITCH) EXCEPT AS	

 CDLOR: WIDTH, STYLE, AND SIZE OF ALL WARKINGS SHALE BE IN ACCORDANCE WITH (MUTCH) EXCEPT AS MODIFIED BY THE PLANS.
 THERMOPLASTIC MARKINGS SHALE BE INSTALLED WHEN THE PAVENUT TEMPERATURE IS 55° F AND RISING. PARTY MARKINGS MAY BE INSTALLED WHEN THE AIR TEMPERATURE IS 50° F AND RISING.

N.Projects\10366\ENG\10366\SPEC01 dgn Default User bharker

## STANDARDS FOR SANITARY SEWER CONSTRUCTION (VILLAGE OF HAMPSHIRE)

- All sanitary sewer construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois", latest edition, and revisions thereto, the notes and on the plans, and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- Sanitary sewers and sewer service shall be constructed of the following materials:
  - Polyvinyl chloride plastic gravity sewer pipe (PVC) conforming to ASTM Designation D-3034 or D-2241 with elastomeric gasket joints conforming to ASTM Designation D-3139. The Standard Dimension Ratio (SDR) for PVC pipe shall be 26 as a minimum and shall be dependent on the depth of cover SDR 26 gravity sewer shall be used for depths up to fifteen (15) feet as measured from the top of the pipe. From fifteen (15) to twently (20) feet SDR 21 pressure-rated pipe conforming to ASTM D-2241 shall be used. At depths greater than twenty (20) feet, PVC pressure-rated pipe shall be used that has a minimum dimension ratio (DR) of 18 and conforms to ASTM D-2241, AWWA C900 or AWWA C 905, whichever is applicable
  - Where ductile iron sanitary sewer pipe is shown on the plans, said pipe shall be ductile iron pipe, class 52, conforming to AWWA C-151 (ANSI 21.51), with joints complying with AWWA C-111 (ANSI A21.11).
- Pipe size shall be a minimum of 8" for sewer mains and 6" for sewer services. Pipe slopes shall be a minimum of 0.40% for 8" sewer and 1.00% for 6" sewer services.
- All sanitary sewer manholes shall be precast reinforced concrete ASTM designation C-478 provided with approved cast in place rubber boots (flexible manhole sleeve) having a nominal wall thickness of three/sixteenths (3/16) inches with a ribbed concrete configuration and with stainless steel binding straps properly sized. All sanitary sewer manholes shall be set in Butyl rope joint sealant, including all component parts, bottoms, barrels, adjusting rings and castings. The outside joints shall be provided with a four (4) inch wide strip of Butyl-Resin Sealant completely around each joint with vertical lap of one (1) inch and horizontal lao of six (6) inches.
- All manhole covers shall have "Sanitary" cast into the top and shall be the concealed pickhole type. All covers used for sanitary sewers shall have a machined surface and a watertight rubber gasket seal. All manhole frames shall be set with Butyl rope joint sealant. Frame and lid shall be Neenah R-1713 with Type B lid or equal.
- 6 A 4' diameter (min.) Inspection manhole shall be constructed outside all buildings for the purpose of flow monitoring. Said manholes shall provide a minimum 5-inch drop from inlet to outlet pipe to facilitate sampling.
- All final adjustments of castings will be accomplished by the use of precast concrete adjusting rings set in Butyl rope joint sealant; mortar joints will not be allowed. Total height of adjusting rings used shall not exceed eight (8") inches. No more than 2 adjusting rings shall be used.
- "SurSeal" chimney seals as distributed by Marathon Materials, Inc. (800/983-9493) or approved equal shall be installed on all manholes.
- Sanitary sewer services may be constructed according to the details on the plans
- 10. When connecting to an existing sanitary main when a tee or wye is not provided, an 'Inserta Tee' fitting must be installed. The minimum distance between fittings is 4 feet center to center. Disruption of any existing sanitary main by breaking or cutting in a wyeltee is prohibited unless the existing main is cracked or broken at the point of connection with 'Inserta Tee'. A representative of the Village shall determine the existing main repair or replacement required on a case by case basis prior to connection, construction or installation.
- Infiltration leakage shall not exceed 200 gallons per inch of pipe diameter per mile per day of sewer pipe, including manholes in the test section.
- All sanitary sewers will be subject to an air exfiltration test, televising test, and deflection test to be performed by the Contractor under the supervision of the Engineer. All testing will be done in conformance with the "Standard Specifications for Water and Sewer Main Construction in Illinois", current edition and Village of Hampshire requirements. In addition all manholes shall be vacuum tested.
- 13. Vacuum testing of each manhole shall be carried out immediately after assembly and prior to backfilling. All lift holes shall be plugged with an approved non-shrink grout.

No grout will be placed in the horizontal joints before testing. All pipes entering the manhole shall be plugged, taking care to securely brace the plugs from being drawn into the manhole.

The test head shall be placed at the inside of the top of the frame section and the seal inflated in accordance with the manufacturer's recommendation.

A vacuum of 10 inches of mercury shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to 9 inches. The manhole shall pass of the time is greater than 60 seconds for a 48" diameter manhole, 75 seconds for a 60" manhole and 90 seconds for a 72" inch manhole.

If the manhole fails the initial test, necessary repairs shall be made with a non-shrink grout while the vacuum is still being drawn. Retesting shall proceed until a satisfactory test is obtained

## STANDARDS FOR SANITARY SEWER SERVICE CONSTRUCTION (VILLAGE OF HAMPSHIRE)

- 1. All sanitary sewer construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois," latest edition, and revisions thereto, the notes on the plans, and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- Sanitary sewers and sewer services shall be constructed of the following materials
- a. Polyvinyl chloride plastic gravity sewer (PVC) conforming to ASTM Designation D-3034 or D-2241 with elastomeric gasket joints conforming to ASTM Designation D-3139. The Standard Dimension Ration (SDR) for PVC pipe snall be 26 as a minimum and shall be dependent on the depth of cover. SDR 26 gravity sewer shall be used for depths up to fifteen (15) as measured from the top of pipe. From fifteen (15) to twenty (20) feet, SDR 21 pressure rated pope conforming to ASTM D-2241 shall be used. At depths greater than twenty (20) feet, PVC pressure rated pipe shall be used having a minimum dimension ration (DR) of 18 and conforming to ASTM D-2241, AWWA C-900, or AWWA C-905, whichever is applicable.
- Where ductile iron sanitary sewer pipe is shown on the plans, said pipe shall be ductile iron pipe, class 52, conforming to AWWA c-141 (ANSI A21.51), with joints complying with AWWA C-111 (ANSI A21.11).
- Pipe size shall be a minimum of 6" for sewer services. Pipe slopes shall be a minimum of 1.00%.
- Sanitary sewer services may be constructed according to the details on the plans.
- Infiltration leakage shall not exceed 200 gallons per inch of pipe diameter per mile per day of sewer pipe, including manholes in the test section.
- 6. When connection to an existing sanitary main when a tee or wye is not provided, an 'inserta Tee' fitting must be installed. The minimum distance between fittings is 4 foot center to center. Disruption of any existing sanitary main by breaking or cutting in a wye / tee is prohibited unless the existing main is broken or cracked at the point of connection with 'inserta Tee'. A representative of the Village shall determine the existing main repair or replacement required on a case by case basis prior to construction or installation.

## STORM SEWER NOTES

## 1. GENERAL:

A. ALL STORM SEMER PIPE SHALL BE RCP. UNLESS OTHERWISE NOTED ON THE PLANS. IN ACCORDANCE WITH THE FOLLOWING:

PLAN CODE: MATERIAL
PRES REIMORCED COMPRETE PIPE LASTM C-16: WITH O-BING GARRIED JOINTS. LASTM C-443: TIPE 1. CLASS IV. PER
SORRE SECTION BOS. ELIPTICAL RCCP PIPE SHALL BE TIPE 1. HE-11: PER SORRE SECTION STI. PRECAST FLABED END
SECTIONS HAVE MASTEL JOINTS. PRIMENTS SHALL BE MADE AT THE CONTRACT UNIT PRICE PER LINEAR FOOD
OF JOHNS SERVER COMPLETE IN PLANCATES SHALL BE MADE AT THE CONTRACT UNIT PRICE PER LINEAR FOOD
OF JOHNS SERVER COMPLETE IN PLANCATES.

DIP: DUTILE IRON WATERMAIN QUALITY PIPE CLASS \$2 (ANS) 21.51: WITH MECHANICAL OF PUSH-ON JOHN'S (ANS) 21.11. DESKYL LINING IS NOT REQUIRED.

PMC: POLITHING CHLORIDE SEMER PIPE, SOR 26. COMPORMING TO ASTM 0-3034 WITH ASTM 0-3212 PUSH-ON GASKETED JOINTS

. HOPE: HIGH DENSITY POLYETHYLENE CORRUGATED PIPS WITH SMOOTH INTERIOR MEETING AASHTO M-294 SUCH AS AGS N-12 BY ADVANCED BRAINAGE SYSTEM, COLUMBUS, DH: OR HI-D BY HANCER, FINDLEY, OH, JOHN'S SHALL BE SEPTI CORRUGATED BANDS BY THE PIPE MANUFACTURER.

UB: RIGID, PERFORATED PYC UNDERDRAIN PIPE (ASTM 0-2723), SOR 35, OR SCHEDUL: 40, WITH SOLVEN FELD DINTS AND FILTER FARRIC WRAPPING OR SOCK. PERFORATED HOPE PIPE

- "BAYO SCAL" OR SIMILAR COUPLINGS SHALL BE USED WHEN JOINING SHALL PIPES OF DISSIMILAR WATERIALS.
  THING SCAL". "FERNCO". AND "MUSSION" TYPE COUPLINGS SHALL NOT BE USED ON SENER WAINS. CHANGES
  IN PIPE MATERIAL SHALL BE WIGHE AT A STRUCTURE.
- C. ALL STORM SEMERS ARE TO BE CONSTRUCTED USING A LASER INSTRUMENT TO MAINTAIN LINE AND GRADE.
- ALL STORM STREETS ARE ID BE CONSTRUCTED USING A LASER INSTRUMENT TO MAINTAIN THE AND GRADE.
   ALL FOOTING ORALIN AND SUMP PUMP DISCHARGE PIPES SHALL BE CONNECTED TO THE STORM SENER SYSTEM. DOWNSPOLIS SHALL DISCHARGE TO THE CROUNDS.
- THE CONTRACTOR SHALL WAINTAIN AT LEAST THREE (3') FEET OF COVER OVER THE TOP OF SHALLOW PIPES AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL MOUND OVER ANY PIPES WHITE LESS THAN THREE 13') FEET OF COVER DURING CONSTRUCTION UNITL HE AREA IS FINAL CRADED OF AVED.

## BEDDING:

A. ALL STOM SCREEN SMALL BE INSTALLED BY A TYPE A SHAMLARD BODING. 1/4" TO J/4" IN SIZE ICA-13 WITH A WINNAM THICANSE COME TO J'AT DOUTS DE DIMETER OF THE SCHEEN PIPE BUT NOT IN SIZE ICA-13 WITH A WINNAM THICANSE COME TO J'AT DEVISION THE REDDING METERALS SMALL BE COMMITTED TO 900 OF WORDED PROPRIED BOSTOM SMALL EXTRACT OF THE PERMICAL BOW ALL REP AND OF PIPE. 30 SIZE OF WORD TO J'AT OFF AND OFF PIPE. SIZE OF WORD TO J'AT OFF AND PIPE. SIZE OF BEDDING SMALL BE CONSIDERED INCIDENTAL TO THE COST OF PIPE. 30 SIZE OFF PIPE. 30 SIZE OFF AND TO JAT OFF AND THE SIZE OFF AND TO JAT OFF AND THE SIZE OFF

## 3. STRUCTURES:

- STUDIOTISS.

  MARROCE, EATER BASIN AND INLET BOTTOMS SHALL BE PRECAST CONCRETE SECTIONAL UNITS OR MORE THE CONCRETE. MARROLES AND CATCH BASINS SHALL BE A MINIMAR "IN DIAMETER UNESS OTHERWISS SPECIFIED DWITE PLANS. STRUCTURE JOINS SHALL BE SEALD WITH DEFINED OR BUTH. CREW. A MAXIMAM OF
- 8. A CONCRETE BENCH TO DIRECT FLOWS SHALL BE CONSTRUCTED IN THE BOTTOM OF ALL INLETS AND MANHOLES.
- C. THE FRAME, GRATE, AND/OR CLOSED LID SHALL BE CAST IRON OF THE STYLE SHOWN ON THE PLANS.
- MANHOLE LIDS SHALL BE MACHINE SURFACED. NON-BOKEING DESIGN. THE CLOSED LIDS SHALL HAVE THE WORD "STORM" CAST ON THE LID. THE JOINTS BETWEEN CONCRETE SECTION ADJUSTING PINGS. AND FRAME SHALL BE SECLED WITH A MANIET COMPOUND.

## 4. FRENCH DRAIN:

A) LION POINT STORM STRUCTURES ARE TO MAYE FOUR IT DIAMETER MESH PROES PROVIDED 24" BELOW THE IDE OF LID. THE HOLES SHALL BE COMERD WITH A DEDICTATION FRANCE CHARMED IN PLACE ATTHE STUDMINGS WASTIC. THE DRAIN SHALL BE ARCFILLED WITH BEDDING OR DA-7 CRUSHED STONE TO TOP DE SUBGRADE OR BOTTOM OF TOPSDIL.

## 5. CASTINGS:

A. CASTINGS FOR SEWER OR OTHER STRUCTURES SHALL BE "NEEMAH" OR APPROVED EQUAL. COST OF CASTINGS SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE STRUCTURE. NO SEPARATE PAYMENT SHALL BE MADE FOR THIS ITEM.

## 6. CLEANING:

A. THE STORM SEWER SYSTEM SHALL BE THOROUGHLY CLEANED PRIOR TO FINAL INSPECTION AND TESTING.

## 7. TELEVISING:

A. THE STORM SEWER SYSTEM SHALL BE TELEVISED IF REQUIRED BY MUNICIPALITY.



SPECIFICATIONS
PET-AG AT HAMPSHIRE GROVE
BUSINESS CENTER
HAMPSHIRE, ILLINOIS

EVELOPMENT ENGINEERS SURVEYORS

miggin , W 8/39 mycos (19/0), 593 (19/0) separate



ILENAME: 0366SPEC01.DGN

DATE: 09/26/18

SHEET

SP1

## STANDARDS FOR WATER MAIN CONSTRUCTION (VILLAGE OF HAMPSHIRE)

- All water main construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illinois", latest edition, and revisions thereto, these improvement plans and details, special provisions and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- All fittings shall be Compact Ductile Iron and shall conform to AWWA/ANSI C153/A21 53-00. Fittings shall be U.L. Listed Class 350, Tyler, Griffin or approved equal.
- All pipe and fittings shall be cement lined in accordance with AWWA/ANSI C104/A21.4-95.
- All fittings shall be mechanical joint and shall be restrained with Mega Lugs by Ebaa Iron unless otherwise shown on the drawings
- Long radius curves, either horizontal or vertical, may be laid with standard pipe by deflections at the joints. Maximum deflections at pipe joints and laying radius for the various pipe lengths shall be in accordance with AWWA C600-99. When rubber gasketed pipe is laid on a curve, the pipe shall be pined in a straight larginment and then deflected to the curved alignment. Trenches shall be made wider on curves for this purpose.
- Sleeves shall be Smith Blair Omni-Coupling #441 or equal. Sleeves shall be provided at locations shown on the plans or as required. The cost of sleeves is considered as incidental to the cost of the project.
- All gate valves shall have a non-rising stem, shall have a standard 2" square operating nut and shall open in a counter-clockwise direction. Gate valves shall be Mueller Resilient Wedge Gate Valve Cat. No. A-2360-23 in accordance with AWWA C-509-01. Main line valves shall be furnished with mechanical joint connections and restrained with Mega Lugs.
- All Valve Boxes shall be cast iron, two piece 5 1/4-inch shafts, Screw-type Tyler Model 666-S. Lids to be marked "Water" (valve box extensions if required are considered incidental). All boxes will be equipped with a rubber stabilizer manufactured by Adapter, Inc.
- All hydrants shall be in accordance with AWWA C502-94 and shall be a Mueller A423 Super Centurion hydrant (break away style traffic design) with one 4 1/2" steamer nozzle and two (2) hose outlets, of which the threads conform with the standards of the Village of Hampshire, libros. The connections between the main line swivel lee to auxiliary valve and auxiliary valve to hydrant
- All pressure taps to an existing village main shall be made with Mueller Mechanical Joint Tapping Sleeve No. H615 and Mueller T2360 Flg x MJ Resilient Wedge Tapping Valve. All should be constructed in a valve vault.
- All tees, bends, valves, and fire hydrants shall be adequately supported with a concrete base, and supported laterally with poured in place thrust blocking against undisturbed earth for all water main with a diameter 16° and greater. Concrete block may be used in lieu of poured in place thrust blocking for all water main with a diameter less than 16°.
- All water mains shall have a minimum depth of cover of 5.5' or as noted on plans
- 14. All water services shall be type "K" copper pipe with compression connections
- All corporation stops shall be Mueller (1" H15008) (1-1/2" & 2" H15013)
- 16 All curb stops shall be Mueller Minneapolis Pattern. (1" H15155) (1-1/2" & 2" B25155)
- All curb boxes shall be Mueller Minneapolis Pattern Base Curb Box. (6' H10300 tapt 2)
- Hydrostatic Tests. The Contractor shall perform Hydrostatic Tests in accordance with Division IV. Section 41 of the Standard Specifications for Water and Sewer Main Construction in Illinois, latest edition, and applicatiop provisions of AWWA C-600 and C-603. The water mains shall be pressure tested at 150 psi. The test pressure shall not drop more than 2 psi for the duration of the test. The gauge shall be of good quality and condition, and be fluid filled. The gauge shall have a large enough range for the pressure being tested and shall be capable of reading a minimum pressure increment of 2 psi. Allowable leakage shall be as set forth in AWWA C-600 lates detilion. The testing length shall be limited to 1000 foot. If more than 1000 foot of watermain is tested, the allowable leakage will be based upon 1000 foot. The duration of the test shall be for two hours minimum.
- Disinfection of the Water Mains Upon completion of the newly laid water mains (and water service lines 4" and larger), the water mains shall be disinfected in accordance with the American Water Works Association, Procedure Designation, AWWA C-651, tiestle action. The responsible for collecting samples and having bacteriological testing performed as required by the IEPA. The Contractor shall furnish to the Village the required documentation, test results, etc., required by the IEPA before placing the water mains in service or before opening a water service line to the Village system.
- 20. All water mains and water service lines shall be protected from sanitary sewers, storm sewers, combined sewers, house sewer service connections and drains in accordance with <u>Title 35</u>; <u>Environmental Protection Agency Subtlet F. Public Water Supplies, Chapter II: Environmental Protection Agency, Paris 651-654 Technical Policy Statements, Section 653.119.</u>
- 21. No water service taps shall be made prior to Village receiving the IEPA operating permit

- STANDARDS FOR WATER MAIN SERVICE CONSTRUCTION

  (VILLAGE OF HAMPSHIRE)

  All water main construction shall be in accordance with the "Standard Specifications for Water and Sewer Main Construction in Illimois," latest edition, and revisions thereto, these improvement plans and details, special provisions and in accordance with codes and ordinances of the Village of Hampshire, Illinois.
- All water services shall have a minimum depth of cover of 5.5' or as noted on plans
- 3 All water services shall be type "K" copper pipe with compression connections.
- All corporation stops shall be Mueller. (1" H15008) (1-1/2" & 2" H15013)
- 5. All curb stops shall be Mueller Minneapolis Pattern. (1" H15155) (1-1/2" & 2" B25155)
- 6. All curb boxes shall be Mueller Minneapolis Pattern Base Curb Box. (6' H10300 tapt 2)
- All water mains and water service lines shall be protected from sanitary sewers, storm sewers, combined sewers, house saver service connections and drains in accordance with Title 35. Environmental Protection Agency Subtilité 7: Public Water Supplies, Chapter II; Environmental Protection Agency, Parts 951-654 Technical Policy Statements, Section 653.119.

## AWWA STANDARD 651-05 SECTION 4.7: DISINFECTION PROCEDURES WHEN CUTTING INTO OR REPAIRING EXISTING MAINS

The following procedures apply primarily when existing mains are wholly or partially dewatered After the appropriate procedures have been completed, the existing main may be returned to service prior to completion of bacteriological testing in order to minimize the time customers are service prior to completion of patients of service prior to completion to extend the service service prior to completion of out of water. Leaks or breaks that are repaired with clamping devices while the mains remain full of pressurized water may present little danger of contamination and therefore may not require disinfection.

## Sec. 4.7.1 Trench Treatment

When an existing main is opened, either by accident or by design, the excavation will likely be wet and may be badly contaminated from nearby sewers. Liberal quantities of hypochlorite applied to open trench areas will lessen the danger from this pollution. Tablest have the advantage in this situation, because they dissolve slowly and continue to release hypochlorite as water is pumped from the excavation

## Sec. 4.7.2 Swabbing With Hypochlorite Solution

The interior of pipe and fittings (particularly couplings and sleeves) used in making the repair shall be swabbed or sprayed with a 1 percent hypochlorite solution before they are installed.


Thorough flushing is the most practical means of removing contamination introduced during repairs. If valve and hydrant locations permit, flushing toward the work location from both directions is recommended. Flushing shall be started as soon as the repairs are completed and shall be continued until discolored water is eliminated.

## Sec. 4.7.4 Slug Chlorination

Where practical, in addition to the procedures previously described, the section of the main in which the break is located shall be isolated, all service connections shut off, and the section flushed and chlorinated as described in Sec. 4.4. The dose may be increased to as much as 300 mg/L and the contact time reduced to as little as 15 min. After chlorination, flushing shall be resumed and continued until discolored water is sliminated and the chlorine concentration in the water exiting the main is no higher than the prevailing water in the distribution system or that which is acceptable for domestic use.

## Sec. 4.7.5 Bacteriological Samples

Bacteriological samples following procedures in 5.1.3 shall be taken after repairs are completed Bacteriological samples following procedures in 5.1.3 shall be taken after repairs are completed to provide a record for determining the procedure's effectiveness. If the direction of flow is unknown, then samples shall be taken on each side of the main break. If positive bacteriological samples are recorded, then the situation shall be evaluated by the purchaser who can determine corrective action. Daily sampling shall be continued until two consecutive negative samples are recorded.



GROVE SPECIFICATIONS
T-AG AT HAMPSHIRE GI
BUSINESS CENTER
HAMPSHIRE ILLINOIS PET



10366SPEC02.DG

0366

SP2

N. Projects\10366\ENG\10366SPEC02.dgn Default User bbarker

This Soil Erosion & Salment Control (\$550) Plan has been zeroed to fait in one of the requirements of the Various Pollutaria (\$550) Plan has been zeroed to fait in one of the requirements of the Various Pollutaria (\$550) Plan has been added to the soil of the Salment (\$550) Plan has been added to the Salment (\$550) Plan ha

A. The following is a description of the nature of the construction activity: Site construction for industrial building-

The following is a description of the intended sequence of construction activities which will disturb soils for major portions of the construction site:

Describe proposed construction sequence, sample follows:

Jestines independent administration sequence, sample in lose:

Ji hardia Farihetta sidiment control measures:

Ji Selective vegetation featural for silt fence installation:

Ji Silf fence installation:

all Construction fencing around areas not to be disturbed distributed on the construction fencing around areas not to be disturbed distributed;

Ji Stilf fence construction entrance

Ji Clear and grub last necessary:

Ji Strip trespit, stabbile topooli and grade site

Ji Temporarily stabilizations in stocchi lesi Seed and silt fence around toe of slope)

Ji Reproversity stabilization seed including last seed and silt fence around toe of slope.

Ji Reproversity stabilization seed including last sheet nove feached base grade.

Ji Reproversity stabilization seed including last sheet nove feached base grade. The site has a total acreage of approximately approximately 15.50 acres. Construction activity will disturb approximately 15.50 acres of the site.

D. 11 An estimated runoff coefficient of the site ofter construction activities are completed is 0.90.

Refer to Sheets <u>DRI</u>_SE3 for a site plan indicating:
1) drainage parterns;

It is altrogated that it is altrogated before and after major grading potivities;
31 locations share vahioles enter or exit the site and controls to minimize off-site sediment tracking;
31 maps of solid distrogates;
32 maps of solid distrogates;
33 maps of solid distrogates;
34 maps of solid distrogates;
35 maps of solid distrogates;
36 maps of solid distrogates;
36 maps of solid distrogates;
37 maps of solid distrogates;
38 maps of solid distrogates;
39 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
32 maps of solid distrogates;
33 maps of solid distrogates;
34 maps of solid distrogates;
35 maps of solid distrogates;
36 maps of solid distrogates;
37 maps of solid distrogates;
38 maps of solid distrogates;
39 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
32 maps of solid distrogates;
33 maps of solid distrogates;
34 maps of solid distrogates;
35 maps of solid distrogates;
36 maps of solid distrogates;
37 maps of solid distrogates;
38 maps of solid distrogates;
39 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
32 maps of solid distrogates;
33 maps of solid distrogates;
34 maps of solid distrogates;
35 maps of solid distrogates;
36 maps of solid distrogates;
37 maps of solid distrogates;
38 maps of solid distrogates;
39 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;
32 maps of solid distrogates;
33 maps of solid distrogates;
34 maps of solid distrogates;
35 maps of solid distrogates;
36 maps of solid distrogates;
37 maps of solid distrogates;
38 maps of solid distrogates;
39 maps of solid distrogates;
31 maps of solid distrogates;
31 maps of solid distrogates;

. It The name of the receiving water(s) islane): Widmayer Road Ditch.
2) The name of the ultimate receiving water is: Coon Creek.
3) The extent of wetland acreage at the site is 6.00 cores.

Potential sources of pallution associated with this construction activity may include: — sediment from disturbed soils

solvents solvents solvents solvents detergers fertilizers cow noterlor despiris large, bagged portland pattent) landscape word depris landscape with and concrete trucks littler.

2. CONTROLS

This section of the XSC Plan addresses the various controls that should be implemented for each of the major anximum to section the section of the Stip base in the stip of the Stip base in the stip of the Stip base in the Stip

A. Approved State or Local Plans

The management prochices, controls and other provisions contained in the SMPPP should be at least as protective as the requirements contained in the Illinois Environmental Protection Agency's (IEPA) and the United Startes Seportment of Agriculturals Assurbed Assurbed Schoen and the Illinois Startes Seportment of Agriculturals Assurbed Assurbed Startes Seportment of Agriculturals Assurbed Assurbed Startes Seportment of Agriculturals Assurbed Startes Seportment of Assurbed Startes Startes Startes Seportment Startes Startes

The soil erosion and sadiment control measures for this site should meet the requirements of the following agencies:

Best Management Practices will be implemented on an as-needed basis to protect water quality. Per ineter controls of the site should be installed prior to soil disturbance lexicularing soil disturbance necessary to install the controls, including the site should be circlely adminished with it find stabilization of those portions of the site upward of the per inster control. Stabilized construction entroles including second should be installed as described in the intended sequence of construction entroles and expenses of the site of the second sequence of construction entroles and the second sequence of construction entroles. The second sequence of construction entroles are sequenced construction entroles as the sequence of construction entroles. See the second sequence of construction entroles are sequenced construction entroles.

Stopilization measures should be initiated where construction activities nove temporarily or perfamently bedsed, apparature with load and State requirements, as described below. Once construction activity in an area has permanently debads, that area should be permanently stabilized. Temporary perfiate controls should be removed after final stabilization of those portions of the site upward of the perimeter controls.

The appropriate soil erasion and sediment controls should be implemented on site and should be modified to reflect the current bhase of construction. All temporary sediment and erasion control measures should be reported as reasoned as son as practicable to equinted my MOSS compliance. Permittee of maintainable appliants in reasonable for inspecting all sediment and erasion control measures or a shirtum of every? calendar days and within 24 hours of the end of a Distriction or greater if can ever to exhaust or showfull equipment.

Unless otherwise indicated, all vegetative and structural erasion and seatment control practices should be installed to the Stondard Proctice. The contractor is responsible for the installation of any additional erasion and seatment contro measures necessary to minimize erasion and seatmentation as determined by the Engineer or Primary Enforce.

1) Stebilization Prostices, large, that will not be pased or opered with non-arcsive staterial should be stabilized using procedures in abstantial conformance with the Illinois laterous stands. In SEC Plan includes a ste-specific soil erosion and sedient control meourses. Additional erosion controls should be implemented as necessory, as determined by the forlineer or Primary Control.

The following temporary and permanent stabilization practices, at a minimum, are proposed:

la) Where the initiation of stabilization measures by the 19th day after construction cativity temporarily or permanently beased is precluded by show covery stabilization measures shall be initiated as soon as practicable-

b) Where construction activity will resume on a partian of the site within 21 days from when activities cased, i.e.g., the tool time period that construction activities is temporally acceded is issued how 21 days then construction of the period to the construction of the period to the construction activity temporarily access.

2) Structural Practicas - Provided value is a description of structural practices that should be implemented to the degree attained to structural present passes of the size of the structural practices should be placed on up and sold in the size of the siz

- stabilized construction entrance - silt fence

D. Storm Water Wanagement

Provided below is a description of measures that will be installed during the construction process to control the pollutants in storm water discharges that will occur after the construction operations have been completed. The installation of these devices may be support to Section 400 of the Clean Water Allow.

1) The prooffices safected for implementation were determined on the coasis of fearnical guidance contained in [29% Fillinois droom Manual, Tederal, State, and/or Local Requirements. The storm woter management measures included.

— determined passins (swisting web costin)

agrammion dasine testaming est positivity. Set Velocity displayment and sections on texts socialized and displayment and sections on texts socialized and displayment and disp E. Waste Wanagement

E. Maste Monogement
Solid assiste nethericals including troots construction debris, excess construction materials, machinery, tools and other
items will be collected and disposed of off sife by the contractor. The contractor is responsible to account the permit
required for such disposals. Burning on site will not be permit read. No solid amorphisms controlled the contractor is responsible to account the permit
should be disposale such disposals. Burning on site will not be permit read. No solid amorphisms controlled the controlled of the control

. Concrete Woste Monagament

Concrete waste or washout should not be allowed in the street or allowed to report a storm water drainage system or watercopyries. Amen proditiopale, a sign should be posted at about location to identify the washout. To the extent proditionals, concrete waterus create should be recorded or response elistance three or stainar welfer of safinger initial or watercopyries, and should be topoted at least of the white or the concrete water concrete the many of the concrete should be installed in about some or some of the concrete their weets it limited broad water or some or some or installed at each washout order.

The containment facilities should be of sufficient volume to completely contain all liquid and concrete waste materials including enough paged by for smitigated levels of rainwater. The dried concrete waste material should be picked so and disposed of properly when 15% capacity is resembled. Wordered concrete on the properly recycled and seed again on site law appropriately the Engineer or hauled off site to an appropriate (small).

G. Comprate Cutting

. Venicie Starage and Waintenance

4. Vanise Statings and Wolfstenance Ween interest and the service of the control of the service of the servi

. Material Storage and Good Housekeeping

To reduce the risks associated with nazordous noterials an site, nazordous products should be kept in original containers unless they are not re-seatable. The priginal labels and 655, should be estained on site and lift times. Mazordous naterials and all other material on site anould be stored in coordinate with manufacturer or 465 specifications, when disposing of hazorous materials, follow hamptocture or 1000 and 516the recommender methods.

The following good housekeeping practices should be followed on site during the construction project:

An effort should be made to store only enough product required to do the job.

All materials stored on site should be stored in a neat, orderly manner in their appropriate containers and adequately protected from the environment.

Products should be kept in their original containers with the original manufacturer's label. Substances should not be mixed with one another unless recommended by the manufacturer.

Operations should be paserved as necessary to ensure proper use and disposal of materials on site.

Whenever possible, all of a product should be used up before disposing of the container.

Manufacturer's recommendations for proper use and disposal should be followed.

Wanagement of Partable Sanitary Stations

To the extent practicable, portable sonitory stations should be loaded in an orea that does not arcin to any protected natural creas. Waters of the State, or starn water structures and should be canced to the ground to prevent from tipping over. Portable sonitory stations loaded on impervious surfaces should be placed on too of a secondary containment device, or be surrounded by a control sladical tag, or proteing page and the contractor sould not create or allow uson into conditions. Sonitory waste should be disposed of in accordance with applicable State and/or local regulations.

A. Spill Grevention and Clean-Up Procedures

Variatorizer's recommended methods for spill clean-up should be available and site personner should be need aware of the presidents and the location of the information and clean-up supplies. Waterfals and equipment necessary for spill clean-up should be kept in the famorical strongs are on spills. Subject and spill relative should be kept in the famorical strongs are on shift Subject and spill relative should report the spill relative should be spilled to produce should be spilled to produce should be spilled to spill report produce and spill relative should be spilled to spill report produce spilled to spill report produce spilled to spill report produce spilled to spilled to spill report produce spilled to spilled to

Plasmanges of a nazardous substance or bill obused by a skill is quality as a spill of bill into a seconds storm Reer's or Moters of the State and not authorized by the ILBIO permit. If a spill obcurs, notify the Primary Contect interestingth, The construction wise should have the capacity to control, continuin, and retore spills. If they occur, spills should be elected up medicately latter discovery in accordance with MSDS and Should not be unified into state severe drainage interest decreases. A water a first severe into state severe drainage interest decreases, whether at the States.

ipits in excess of Federal Reportable Quantities (as established under 40 ER Parts 110, 117, or 302), should be reported to the National Response Enter by calling (800) 424-8802. MSDs often include information on Federal Reportable Quantities for materials. Spills of fusic or hazardous materials should be reported to the deprecial State or Local government opency, as required. Shen cleaning up a spill, the area should be set well vertilated and operage reposal protective adultment should be used or minimalize injury from contact with a natoratous substatus.

in addition to the good housekeeping and other management practices discussed in the previous sections of these Notes. The following minimum practices should be followed to reduce the risk of spills:

On-site vehicles should be monitored for leaks and should receive regular preventative maintenance to reduce the change of leakage.

Petroleum products should be stored in tightly segled and clearly labeled containers.

Contractors should follow the manufacturer's recommendations for proper use, storage, and disposal of materials. Exass, materials should be disposed of apporting to the manufacturer's instructions or State and Local regulations, and amould not be disported to the storm seem of widerbody.

De-Watering Operations

During de-water ing/pumping operations, only uncontaminated water should be allowed to discharge to protected natural areas, waters of the State, or to a storm sever system (in accordance with Local permiss). Inter hoses should be pload in a stabilized supp by or floaded at the surface of the water in order to limit the amount of sediment inside. Pumping operations may be discharged to a stabilized area that consists of an energy dissipating device (e.g., stone), sediment filter bog, or sobth. Adequate erasian controls should be used during deventing operations an eccasory. Stabilized conveyance channels should be installed to direct water to the desired location as applicables.

M. Off-Site Vehicle Tracking

The site should have one or more stabilized construction entranges in conformance with the Plan details. Stabilized construction entrances is should be installed to help reduce vehicle tracking of sediments. Streets should be seen as mediat for educe seess sediment, diff. or stable tracked from the site. Meinterware may include the or desasting the stability depends on the stability of the stab

N. Topsoil Stockpile Management

If topoli is to be shown let in the site, select a location as that it will not ender allow the location as into it will not ender allow the location as into the location as the state of the state of

pagt control should be implemented on site as meassary. Repetitive fractment should be opplied as headed to goodpollan Control when temporary dust control measures are used. A water truck should be present on site or available to sprink impartingation to their the amount of dust leaving the site. Watering should be appling by or mare frequently to be effective. Courtion should be used not to ownwater, as that may couse reason.

. WAINTENANCE

Epintenance of the controls incorporated into this project should be performed as needed to assure their continued effectiveness. This includes prompt and effective repair analysis replicated to deficient control resources. The following is a sepaiription of proseques that should be used to provident in appoint operating partial and repsign and sadiment control measures and other protective measures (spenified in the SSSS Plan and Standord positionalisms.

bust control: When temporary dust control measures are used, repetitive treatment should be applied as nesded to

Stiff fender: Stiff fendes should be inspected regularly for undercutting where the fende meets the ground, overtopping not stors along the length of the fende. Deficiencies should be repaired immediately. Remove accumulated scalents room the fende speck when the satisfactor fenders cannot not repair and principle of the story o

Irabilizad construction entrance: The stabilizad construction entrances should be maintained to prevent tracking of aditional anto bublic streets. Maintenance includes too dressing with additional stone and retoking too layers of tone and sediment. The sediment franced onto the public right-of-way should be reflowed limeolately.

Temporary sediment frozes and the public right-of-way should be retored immediately frozen and the public right-of-way should be retored immediately controlled and state of the public retored immediately calculated and state of the rate to its inclination in the public retored the public retored to the publ

INSPECTIONS

The Permittee for their authorized representatives will be responsible for conducting sits inspections in compliance with the 1881b BBSS Fermit, After each inspection in a proof should be presented by the person who performed the inspection. The inspection report should be mointained on site is part of the Septem.

ach inspection should include the following components:

Disturbed orioss and areas used for the storage of paterials that are exposed to precipitation build be inspected for evidence of any the potential for, pollutants entering the drainage system, excluding a significant process of the process of th

beard on the require of the impaction, the description of patential solitant fources identified not the pollution revention mesures apported in the SMPP soliton to meries operating the soon as profit icable of the impaction. The modifications, if any, shall provide for sizely implementation only changes to the SMPP within 7 calendor days following the inspection.

c. A report summorizing the scope of the inspection, numetal and qualifications of personnel making the inspection. The date(s) of the inspection, major observations relating to the impresentation of the specific process of the process of the

D. The Permittee should compriste and submit within 5 days on "Incidence of Non-Comprisions" (1904) report for any violation of the SPPP asserted for any mispection conductors, including tools not reported by the Spaints of Non-Comprision of N

All reports of non-compliance small be signed by a responsible authority as defined in Part VI.S. Eighotory Requirements), of the IERIO MPDES Parmit.

All reports of non-compliance and libe moiled to LEPA at the following address:

Hinois Environmental Protection Agency Ivision of Water Pollution Control ompliance Assurance Section 021 North Grand Avenue East 021 North Grand Avenue East 026 Pringfield. Himois 62794–9276

religation arranges. Depotaminated ground waters and, Foundation or spoting drains where flows are not contaminated with process materials such as solvents. lution prevention measures should be implemented for hon-storm water components of the discharge.

STABILIZATION TYPE	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	
PERMANENT SEEDING			+4						-			
DORMANT SEEDING	8		-								, B	
TEMPORARY SEEDING			+c		2777079	-	D		-			
SODDING			Esse						_			
MULCHING	F											

A KENTUCKY BLUEGRASS 90 LBS/ACRE
MIXED WITH PRENNIAL RYEGRASS
30 LBS/ACRE.

150 LBS/ACRE.

150 LBS/ACRE.

30 : BSYACRE.

8 KENTUCKY BULGRASS 135 LBSYACRE E SOD

45 LBSYACRE + STRAW MULCH 2 TOMSYACRE.

F STRAW MULCH 2 TOMSYACRE.

F STRAW MULCH 2 TOMSYACRE.

# IRRIGATION NEEDED DURING JUNE AND JULY.
## IRRIGATION NEEDED FOR 2 TO 3 WEEKS AFTER APPLYING SDD. SOIL PROTECTION CHART

PROJECT: PET-AG AT HAMPSHIRE GROVE BUSINESS CENTER PERMIT #: ILR10 TELEPHONE NUMBER CONTRACTOR SIGNATURE PRINTED NAME & TITLE VAUE OF CONTRACTING FIRM STREET ADDRESS CITY, STATE, ZIP CODE TRADE/ RESPONSIBILITIES:

NOTE: ALL CONTRACTORS PERFORMING WORK ON THIS SITE ARE REQUIRED TO SION A CONTRACTOR CERTIFICATION STATEMENT AS ILLUSTRATED ABOVE. THE SIGNED STATEMENTS WILL BE MAINTAINED ON THE SITE WITH THE SWPPP

DWNER SWPPP CERTIFICATION PROJECT: PET-AD AT HAMPSHIRE DROVE BUSINESS DENTER

PERMIT #: ILRIO ....

SIGNATURE OF OWNER

PRINTED NAME OF DWNER

NOTE: THE CERTIFICATION ILLUSTRATED ABOVE SHALL BE SIGNED BY THE OWNER LISTED ON THE NOTICE OF INTENT IN ACCORDANCE HITH PART VI.S, OF THE ILRID NPDES PERMIT. THE SIGNED STATEMENT SHALL BE MAINTAINED ON THE SITE WITH THE SWPPP-

STORMWATER POLLUTION PREVENTION PLAN
PET-AG AT HAMPSHIRE GROVE
BUSINESS CENTER
HAMPSHIRE ILLINOIS


CONSULTING ENGINEERS SITE DEVELOPMENT ENGINEE LAND SURVEYORS




FILENAME: 0366SE01


09/26/18


SE₁




V Projects/10366/ENG/10366SE02 dgn Default User -bbarker
















ILENAME: IO366DETO2.DGN

0366

D2 13 OF 14









PREMIUM BLUEGRASS MIX 4-5 LBS PER 1,000 SF

20% MIDNIGHT KENTUCKY BLUEGRASS 20% DENIM KENTUCKY BLUEGRASS 20% LANGARA KENTUCKY BLUEGRASS 20% BLUESTAR KENTUCKY BLUEGRASS 10% PRIZM PERENNIAL RYEGRASS 10% SUNSHINE PERENNIAL RYEGRASS

QD/	Common Name	Botenical Name	Size	Remarks	Code
5	Marmo Maple	Acer freemanii 'Marmo'	2 1/2"	B&B	AFM
3	State Street Miyabe Maple	Acer miyabei 'Morton'	2 1/2"	B&B	AMM
9	Princeton Sentry Ginkgo	Ginkgo biloba 'Princeton Sentry'	2 1/3"	B&B	GBPS
3	Espresso Kentucky Coffee Tree	Gymnocladus dioica 'Espresso'	2 1/2	B&B	GDE
8 5	Skyline Locust	Gleditsia triacanthos 'Skyline'	2 1/2"	888	GTS
5	Swamp White Oak	Quercus bicolor	2 1/5"	B&B	QB
3	Regal Prince English Oak	Quercus robur 'Regal Prince'	2 1/5"	888	QRRP#
5	Shawnee Brave Bald Cypress	Taxodium distichum 'Shawnee Brave'	2 1/2"	B&B	TDSB
5	Triumph Elm	Ulmus 'Morton Glossy'	2 1/2"	B&B	UMG
6	Autumn Brilliance Serviceberry	Amelanchier grandiflora	6'	B&B	AGAB
5	Clump River Birch	Betula nigra	10"	B&B	BN
5	Golden Glory Cornelian Cherry	Comus mas 'Golden Glory'	6'	B&B	CMGG
5	Ivory Silk Japanese Tree Lilac	Syringa reticulata 'Ivory Silk'	6'	B&B	SRIS
8	Norway Spruce	Picea abies	6'	B&B	PA
12	Black Hills Spruce	Picea glauca 'Densata'	6'	B&B	PGD
5	Colorado Blue Spruce	Picee pungens 'Glauca'	6'	B&B	PPG
20	Green Gern Boxwood	Bexus 'Green Gem'	18"-24"	Cont	BGG
23	Sunrise Forsythia	Forsythia ovata 'Sunrise'	30°	Cont.	FOS
16	Little Lime Hydrangea	Hydrangea paniculata 'Jane'	18"-24"	Cont	HPJ
57	Happy Returns Daylity	Hemerocaliis 'Happy Returns'	#1		HHR
30		Nepeta faassenii 'Walker's Low'	#1		NEWL

REVISIONS

Dowden Landscape Design
P.O.Box 415, Libertyville, II. 60048
Phone: (847) 362–1254
Email: dowdenassoc@sbcglobal.net

LANDSCAPE PLAN


PET-AG AT HAMPSHIRE GROVE
BUSINESS PARK
FLANNIGAN DRIVE
HAMPSHIRE, ILLINOIS


Date 09.27.18


Scale 1"=50' Drawn CJD

Job Sheet

L - 1.0







PERENNIAL PLANTING

HOT TO SCALE




SHRUB PLANTING

NOT TO SCALE

HILLSIDE PLANTING NOT TO SCALE

EVERGREEN TREE PLANTING **MOT TO SCALE** 

NOT TO SCALE





Dowden Landscape Design

P.O.Box 415, Libertyville, IL, 60048 Phone: (847) 362~1254 Email: dowdenassoc@sbcglobal.net

REVISIONS BY


PLAN

LANDSCAPE

PET-AG AT HAMPSHIRE GROVE
BUSINESS PARK
HAMPSHIRE, ILLINOS
HAMPSHIRE, ILLINOS

Date 09.27.18 Scale 1"=10" Drawn CJD

L - 2.0





1 KEY PLAN
SCALE 1" = 100'-0"

2 SITE PHOTOMETRIC
SCALE 1" = 50'-0"

י פר כל פל 20 בני <del>פל פל</del> 24 פל פ<del>ל כל ול כ</del>ל י 00 00 00 00 00 00 00 00 01 01 02 03 05 07 10 13 86 19 77 74 73 70 ים מס מס מס מר מל וב מב <del>וסא סא</del> וב לבל <del>מל מל בל בל בל בל</del> מל 00 00 00 00 00 00 00 00 01 01 02 03 05 07 10 13 6 18 72 74 73 20 ל כל ספ<u>ל הור פור אור אבל</u> של הל פור ארי - ור פור של כל כל סבר ס ה כל של <u>אבר פבר שב</u>ר צל פור שהי ארי - הר פור מר אל ב 

PHOTOMETRIC STATISTICS AVERAGE MINIMUM UNIFORMITY RATIO CAR PARKING 2.1fc 0.5fc 4.2:1







40 S. ADDISON ROAD ADDISON, IL 60101 630-543-9059 www.connellyelectric.com

NORTHERN BUILDERS 5060 RIVER ROAD SCHILLER PARK, IL 60176 847-678-5060



NO.	DESCRIPTION	DATE
△	ISSUED FOR PERMIT	09/28/2018

PET-AG


HAMPSHIRE GROVE **BUSINESS CENTER** HAMPSHIRE, IL


# SITE **PHOTOMETRIC**

PROJECT NUMBER	18-0000
DATE	09/28/2018
DRAWN BY	AB
CHECKED BY	JDO

E101


CALLOUT	SYMBOL	DESCRIPTION	MODEL	TOTAL VA	VOLTS
S1	Ō	SHOE BOX LED WALL MTD. FIXTURE	LITHONIA DSX1-LED-P8-40K-T4M-MVOLT-WBA-DDBXD	207	277V 1P 2W
S3	DC	DOUBLE HEADEDLED SHOE BOX FIXTURES MOUNTED ON A 25'-0" POLE	LITHONIA (2) DSX1-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE. SSS-25-4C-DM28-PL-DDB	414	277V 1P 2W
S4		DOUBLE HEADEDLED SHOE BOX FIXTURES MOUNTED ON A 25'-0" POLE	LITHONIA (2) DSX1-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE: SSS-25-4C-DM28-PL-DDB	414	277V 1P 2W





SITE LIGHTING PLAN
SCALE 1" = 50'-0"

PHOTOMETRIC STATISTICS UNIFORMITY RATIO MINIMUM 0.5fc CAR PARKING 2.1fc 4.2:1



CALLOUT	SYMBOL	DESCRIPTION	MODEL	TOTAL VA	VOLTS
S1	Ď	SHOE BOX LED WALL, MTD. FIXTURE	LITHONIA DSX1-LED-P8-40K-T4M-MVOLT-WBA-DDBXD	207	277V 1P 2W
53	D+0	DOUBLE HEADEDLED SHOE BOX FIXTURES MOUNTED ON A 25'-0" POLE	LITHONIA (2) DSX1-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE: SSS-25-4C-DM28-PL-DDB	414	277V 1P 2W
S4	₽_	DOUBLE HEADEDLED SHOE BOX FIXTURES MOUNTED ON A 25'-0" POLE	LITHONIA (2) DSX1-LED-P8-40K-T4M-MVOLT-SPA-DDBXD POLE: SSS-25-4C-DM28-PL-DDB	414	277V 1P 2W



40 S. ADDISON ROAD ADDISON, IL 60101 630-543-9059 www.connellyelectric.com

NORTHERN BUILDERS 5060 RIVER ROAD SCHILLER PARK, IL 60176 847-678-5060



NO.	DESCRIPTION	DATE
△	ISSUED FOR PERMIT	09/28/2018

## PET-AG

HAMPSHIRE GROVE **BUSINESS CENTER** HAMPSHIRE, IL

## SITE LIGHTING **PLAN**

PROJECT NUMBER	18-0000
DATE	09/28/2018
DRAWN BY	АВ
CHECKED BY	JDO

E102



October 3, 2018

Plan Commission and Village Board Village of Hampshire 234 S. State Street P.O. Box 457 Hampshire, IL 60140-0457

Re:

Preliminary Plan and Plat Review Old Mill Manor Unit 11 - Lazar Village of Hampshire

#### Ladies and Gentlemen:

We have reviewed the following items:

- Preliminary Site Plan for Lot 1 and 2 dated August 2, 2018 and prepared by Scheflow Engineers.
- Preliminary Plat for Lot 1 and 2 dated July 25, 2018 and prepared by Scheflow Engineers.
- Preliminary Entrance Plan dated August 2, 2018 and prepared by Scheflow Engineers.
- Plat of Survey dated February 23, 2016 and prepared by Alan J. Coulson, P.C.

Our review of these plans is to generally determine compliance with local ordinances and whether the improvements will conform to existing local systems and equipment. This review and our comments do not relieve the designers from their duty to conform to all required codes, regulations, and acceptable standards of engineering practice. Engineering Enterprises, Inc.'s review is not intended as an in-depth quality assurance review; we cannot and do not assume responsibility for design errors or omissions in the plans. As such, we offer the following comments:

## General

 The resubdivision of Unit 11 will require approval by the Plan Commission and Village Board.

- The following shall be submitted as part of final engineering:
  - Landscape Plan
  - Lighting and photometric plan
  - Striping plan that meets parking space requirements
  - Geotechnical report
- 3. The developer should contact the Village's building department to determine the submittals required for their review and approval.

### Preliminary Plan

- 4. The following shall be added to the preliminary plans:
  - Legend
  - A minimum of two benchmarks plus datum used
  - Name and address of the owner and subdivider
  - Finished floor (FF) elevations of the proposed buildings
  - Proposed grading and drainage information
  - Typical section for the proposed pavement
- 5. According to the recorded Final Plat of Old Mill Manor Unit 11, no buildings, fences, plantings or obstructions shall be allowed within the ingress and egress easement. Currently the trash enclosure is encroaching on the easement.
- 6. The access road should be extended to the east property line.
- 7. The driveway approach shall be 8" of PCC over 6" of aggregate base.
- 8. It is unclear if curb and gutter is being proposed. Curb and gutter will be required throughout and should be shown.
- 9. We recommend public sidewalk be installed along the south frontage of the development to allow for pedestrian access to the future businesses. The proposed sidewalk will need to be permitted through IDOT if the new sidewalk is proposed to be within the State ROW.
- 10. The developer should confirm the need for 8" water services to each building in lieu of a 6" water service.
- 11. It is the Village's intent to abandon the existing dead end 8" water along IL Route 72. Therefore, the proposed water main shall be looped to the existing 6" water main (shown as 8"; to be revised) located north of the site.

#### <u>Transportation</u>

- 12. IL Route 72 is under the jurisdiction of the Illinois Department of Transportation (IDOT). IDOT will be responsible for issuing access permits along this roadway. Comments from IDOT concerning the Preliminary Plan should be provided upon receipt. It is our understanding that these have been submitted.
- 13. Internal turning movement exhibits should be provided during final engineering to confirm truck movements.

#### **Stormwater Management**

- 14. The detention basin in the Old Mill Manor development was designed and approved according to the previous version of the Village's Stormwater Ordinance and Unit 11 of this development has been listed as exempt from the stricter design criteria of the current stormwater ordinance. The proposed development is consistent with the original overall Old Mill Manor preliminary plat and therefore no additional stormwater detention is necessary.
- 15. Storm sewer capacity design calculations shall be submitted with final engineering. The storm sewer will be connected to an existing storm sewer that outfalls into the Old Mill Manor development detention basin. The capacity of the existing storm sewer shall be determined and on-site detention provided if necessary based on the capacity of the storm sewer. Overland overflow flood routing will also need to be provided with Final Engineering.
- 16. Due to a project disturbance greater than 5,000 SF, a complete Kane County Stormwater Management Permit Application with supporting documentation shall be submitted as part of final engineering. The applicant should refer to the submittal checklist to ensure that all required supporting documentation is submitted.
- 17. A Stormwater Pollution Prevention Plan (SWPPP) in accordance with the IEPA NDPES General Construction Permit ILR10 requirements needs to be included in the final engineering plans and the Notice of Intent (NOI) submitted to the IEPA before construction. The Illinois Historic Preservation Agency (IHPA) sign-off and Illinois Department of Natural Resources (IDNR) endangered species review (EcoCAT) sign-off will also be required as part of the NOI permit.

#### **Preliminary Plat**

- 18. The following shall be added to the preliminary plat:
  - Name of the proposed subdivision
  - Name and address of owner, subdivider, and designer of preliminary plan
  - Legal description of location
  - Minimum front setback lines, with dimensions shown
  - The names of owners of adjacent unplatted land
  - The names of owners of immediately adjacent platted land, together with the subdivision plat by name, recording date and document number
- 19. Setbacks lines with dimensions per the Village Ordinance for the front yard (10'), side yard (5'), and rear yard (20') shall be shown on the plan. In the current design, the rear yard setback is being encroached by one trash enclosure, the parking space, and drive aisle.
- 20. All existing easements need to be labeled as existing.
- 21. The existing 10' Village utility easement needs to be shown on the east property line.
- 22. The measurement of 236.15 is labeled as a record; however, the record dimension is 236.17.

23. A cross access easement between Lots 1 and 2 needs to be delineated or an ingress/egress easement over all paved areas should be provided.

If you have any questions or require additional information, please call our office.

Respectfully submitted,

ENGINEERING ENTERPRISES, INC.

Bradley P. Sanderson, P.E.

Vice President

## BPS/tam/jam

pc: Linda Vasquez, Village Clerk (Via e-mail)

Lori Lyons, Finance Director (Via e-mail)
Mark Schuster, Village Attorney (Via e-mail)

Joe Lazar, LB Five LLC (Via e-mail)

Frank Cuda, Scheflow Engineers (Via e-mail)

JAM, EEI (Via e-mail)



October 3, 2018

Plan Commission and Village Board Village of Hampshire 234 S. State Street P.O. Box 457 Hampshire, IL 60140-0457

Re:

Preliminary Plan and Plat Review Old Mill Manor Unit 10 - Lazar Village of Hampshire

Ladies and Gentlemen:

We have reviewed the following items:

- Preliminary Site Plan for Lot 1 and Lot 2 dated August 2, 2018 prepared by Scheflow Engineers.
- Preliminary Plat for Lot 1 and 2 dated August 2, 2018 prepared by Scheflow Engineers.
- Preliminary Widening Plan for Route 72 dated August 2, 2018 prepared by Scheflow Engineers.
- Plat of Survey dated February 23, 2016 prepared by Alan J. Coulson, P.C.

Our review of these plans is to generally determine compliance with local ordinances and whether the improvements will conform to existing local systems and equipment. This review and our comments do not relieve the designers from their duty to conform to all required codes, regulations, and acceptable standards of engineering practice. Engineering Enterprises, Inc.'s review is not intended as an in-depth quality assurance review; we cannot and do not assume responsibility for design errors or omissions in the plans. As such, we offer the following comments:

### General

1. The resubdivision of Unit 10 will require approval by the Plan Commission and Village Board.

- 2. The following shall be submitted as part of final engineering:
  - Landscape Plan
  - Lighting and photometric plan
  - Striping plan that meets parking space requirements
  - Geotechnical report
- 3. The developer should contact the Village's building department to determine the submittals required for their review and approval.

## **Preliminary Plan**

- 4. The following shall be added to the preliminary plans:
  - Legend
  - A minimum of two benchmarks plus datum used
  - Name and address of the owner and subdivider
  - HWL of the detention pond (902.00)
  - Finished floor (FF) elevations of the proposed buildings
  - Proposed grading and drainage information
  - Typical section for the proposed pavement
- According to the recorded Final Plat of Old Mill Manor Unit 10, no buildings, fences, plantings or obstructions shall be allowed within the ingress and egress easement. Currently the corner of Building 1 and the trash enclosures are encroaching on the easement.
- 6. The driveway approach shall be 8" of PCC over 6" of aggregate base.
- 7. It is unclear if curb and gutter is being proposed. Curb and gutter will be required throughout and should be shown.
- 8. We recommend public sidewalk be installed along the south frontage of the development to allow for pedestrian access to the future businesses. The proposed sidewalk will need to be permitted through IDOT if the new sidewalk is proposed to be within the State ROW.
- 9. The existing water main along the northern limits is an existing 6" water main. The proposed pressure connections should be reduced to 6" valves.
- 10. The water service pressure connection for Lot 1 should be shifted east in order to accommodate a valve vault that does not conflict with the existing water main tee and valve vault.
- 11. The developer should confirm the need for 8" water services to each building in lieu of a 6" water service.
- 12. The fire hydrant lead for the existing fire hydrant southeast of Lot 2 should be shown.
- 13. The existing water main that runs east-west along IL Route 72 should be called out as 12".

14. As part of the 2011 utility improvements for Unit 10, sanitary sewer service stubs were provided for Lots 3 through 6. These stubs should be utilized for the proposed buildings. Additionally, the stubs not utilized should be removed as part of the proposed development.

### **Transportation**

- 15. IL Route 72 is under the jurisdiction of the Illinois Department of Transportation (IDOT). IDOT will be responsible for issuing access permits along this roadway. Comments from IDOT concerning the Preliminary Plan should be provided upon receipt. It is our understanding that these have been submitted.
- 16. Internal turning movement exhibits should be provided during final engineering to confirm truck movements.

## Stormwater Management

- 17. The detention basin in the Old Mill Manor development was designed and approved according to the previous version of the Village's Stormwater Ordinance and Unit 10 of this development has been listed as exempt from the stricter design criteria of the current stormwater ordinance. The proposed development is consistent with the original overall Old Mill Manor preliminary plat and therefore no additional stormwater detention is necessary.
- 18. Storm sewer capacity design calculations shall be submitted with final engineering.
- 19. Due to a project disturbance greater than 5,000 SF, a complete Kane County Stormwater Management Permit Application with supporting documentation shall be submitted as part of final engineering. The applicant should refer to the submittal checklist to ensure that all required supporting documentation is submitted.
- 20. A Stormwater Pollution Prevention Plan (SWPPP) in accordance with the IEPA NDPES General Construction Permit ILR10 requirements needs to be included in the final engineering plans and the Notice of Intent (NOI) submitted to the IEPA before construction. The Illinois Historic Preservation Agency (IHPA) sign-off and Illinois Department of Natural Resources (IDNR) endangered species review (EcoCAT) sign-off will also be required as part of the NOI permit.

## Preliminary Plat

- 21. The following shall be added to the preliminary plat:
  - Name of the proposed subdivision
  - Name and address of owner, subdivider, and designer of preliminary plan
  - Legal description of location
  - Minimum front setback lines, with dimensions shown
  - The names of owners of adjacent unplatted land
  - The names of owners of immediately adjacent platted land, together with the subdivision plat by name, recording date and document number

- 22. Setbacks lines with dimensions per the Village Ordinance for the front yard (10'), side yard (5'), and rear yard (20') shall be shown on the plan. In the current design, the rear yard setback is being encroached by the trash enclosures and drive aisle.
- 23. All existing easements need to be labeled as existing.
- 24. The new road alignment is out of the access easement. Additional area needs to be added to the easement to cover the drive.
- 25. A cross access easement between Lots 1 and 2 needs to be delineated or an ingress/egress easement over all paved areas should be provided. The latter would resolve the issue noted in comment No. 24.

If you have any questions or require additional information, please call our office.

Respectfully submitted,


ENGINEERING ENTERPRISES, INC.


Bradley P. Sanderson, P.E.


Vice President


## BPS/tam/jam

pc: Linda Vasquez, Village Clerk (Via e-mail)
Lori Lyons, Finance Director (Via e-mail)
Mark Schuster, Village Attorney (Via e-mail)
Joe Lazar, LB Five LLC (Via e-mail)
Frank Cuda, Scheflow Engineers (Via e-mail)
JAM, EEI (Via e-mail)











September 12, 2018

Plan Commission and President and Board of Trustees Village of Hampshire 234 S. State Street P.O. Box 457 Hampshire, IL 60140-0457

Re:

Tri County Self Storage - Concept Plan Review

Village of Hampshire Kane County, Illinois

Ladies and Gentlemen:

We have reviewed the Concept Plan (1 sheet), undated, prepared by Trotter and Associates, Inc. for the above referenced project.

Our review of these plans is to generally determine the plan's compliance with Village ordinances and whether the improvements will conform to existing Village systems and equipment. This review and our comments do not relieve the designer from his duties to conform to all required codes, regulations, and acceptable standards of engineering practice. Engineering Enterprises, Inc.'s review is not intended as an in-depth quality assurance review, we cannot and do not assume responsibility for design errors or omissions in the plans. We offer the following comments:

- 1. This is a cursory review of the Concept Plan and detailed review will be completed when Final Engineering Plans and supporting documentation is submitted for review. Additional review comments will be issued as submittals are received.
- 2. As part of Final Engineering, the project will require permits and submittals to the following agencies as appropriate.
  - > IEPA for Storm Water Pollution Control.
  - > IDNR for Threatened and Endangered Species
  - > IHPA for Cultural Resources
  - > IDOT for connection to and improvements in Route 20 ROW
  - > USACE and/or Kane County for wetland impacts
- A Storm Water Permit Application and supporting calculations in accordance with the Village Ordinance will be required. Ideally, storm water management facilities for the entire development will be coordinated. Note that a wetland delineation and drain tile survey will also be required.
- 4. A tree survey and landscape plan will be required as part of Final Engineering.

Plan Commission and President and Board of Trustees September 12, 2018 Page 2

- 5. A traffic impact study may be required for the overall development to determine the extent of transportation related improvements.
- There is currently no Village water main or sanitary sewer service to the property. Service to the site should be discussed with annexation. Well and septic permits may have to be obtained from the Kane County Health Department.
- 7. An Annexation Plat and Plat of Subdivision will have to be prepared and submitted for review.

The developer should provide the requested information and make the necessary revisions and submit two (2) plans for further review. If you have any questions or require additional information, please call our office.

Respectfully submitted,

ENGINEERING ENTERPRISES, INC.

Bradley P. Sanderson, P.E.

Vice President

#### **BPS/TNP**

Linda Vasquez, Village Clerk (Via e-mail) pc: Lori Lyons, Finance Director (Via e-mail)

Mark Schuster, Village Attorney (Via e-mail)

Dale V. Marting, Trotter and Associates, Inc. (Via-email)

Tom Burney, Zanck, Coen, Wright & Saladin, P.C. (Via-email)

JAM, EEI (Via e-mail)

